

**TENDER SCHEDULE**

<b>NAME OF THE WORK:-</b>	<b>CONSTRUCTION OF OF ACR AT UPPER MANIA UPS UNDER SEMILIGUDA BLOCK</b>
<b>SCHEME</b>	<b>DMF 2018-19</b>
<b>ESTIMATED COST</b>	<b>Rs. 7,72,000/-</b>
<b>AMOUNT PUT TO TENDER</b>	<b>Rs. 5,77,347/-</b>
<b>COST OF TENDER PAPER</b>	<b>Rs. 4,000/-</b>
<b>E.M.D REQUIRED</b>	<b>Rs. 5,800/-</b>
<b>PERIOD OF COMPLETION</b>	<b>06 Months</b>

Sl. No.	Description	Quantity	Unit	Rate(in Rs)	Amount in Rs.
1	Earth work excavation in foundation tranches in hard soil except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away form the site with all leads and lifts. T&P shoring and shuttering if required etc. complete as directed by Engineer-in-Charge.	29.12	Cum	169.80	4,944.89
2	Supply and filling of sand in foundation and tranches with well waterd and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost of sand, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour, sundries. T&P required for the work complete including dewatering if required as epr instruction of Engineer-in-Charge.	30.13	Cum	334.80	10,088.13
3	Providing & laying Plain Cement Concrete 1:4:8 (1Cement 4 fine aggregate and 8 course aggregate (40 mm CB metal) in foundation and plinth including cost of hoisting, lowering laying concrete, ramming, and curing etc. complete to required levels laid in layers not exceeding 15 cm thick including cost. conveyance, loading and unloading, royalties and taxes all materials and cost of allll labours, sundreies T & P required for the work complete including dewatering if required as per instruction of Enginner-in-Charge.	21.16	Cum	3660.70	77,477.63
4	RR Stone Masonary in Cement Mortar of (1:6) with portland slag cement, watering and curing etc including cost, conveyance, loading and unloading, royalties and taxes of allll material and cost of labour sundries T&P required for the works etc complete in all respect as directed by the Enginnr-in-Charge.	13.21	Cum	2847.70	37,610.51
5	CB Brick work masonry in super structure in ground floor throughly soked in water with cment mortar (1:6) including necessary scaffolding, racking out joints, curing etc. complete as per specification and direction of the Engineer-in-Charge.	18.19	Cum	3313.70	60,279.49

*[Handwritten signature]*

Sl. No.	Description	Quantity	Unit	Rate(in Rs)	Amount in Rs.
6	i. Provide, lifting, jacking, laying reinforced cement concrete of M20 grade in column footing, as per approved drawings and drawings having a minimum compressive strength (in works test) 200 kg/square cm in 15 cm. Cubes at 28 days curing, after mixing and tests conducted in accordance with I.S 416 using 12mm to 20 mm size black hard crusher broken granite stone chips of approved quality from approved quarry washed and cleaned (20mm size not to exceed 25 %) to be mixed in concrete mixture with ordinary portland cement (OPC) including centering and shuttering, noisting, lowering complete in all respect as per specification and direction of the Engineer-in-Charge.				
a	Column base	8.26	Cum	4565.50	37,729.48
b	Plinth Bend	1.89	Cum	4,878.10	9,201.91
c	Column	1.66	Cum	8818.40	14,669.49
d	Lintel,	1.38	Cum	7471.30	10,327.41
e	Chajjas	0.50	sqm	10290.60	5,132.82
f	Roof beam	1.85	Cum	8818.40	16,330.63
g	Roof slab	6.23	Cum	7893.70	49,216.82
7	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, tools etc. complete in all respect as per the direction of Engineer-in-Charge.	23.60	Qtl	5059.20	1,19,380.07
8	25 mm thick Grading Concrete with CC (1:2:2) over roof slab, curing, laying, concrete etc in complete in all respect as per the direction of Engineer-in-Charge.	62.02	Sqm	227.30	14,097.68
9	12mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary scaffolding, curing, etc, complete in all respect as per the direction of Engineer-in-Charge.	122.27	Sqm	100.40	12,276.22
10	16mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curing, etc complete in all respect as per the direction of Engineer-in-Charge.	96.89	Sqm	143.00	13,855.94
11	Fixing of kota tiles in floors, trades or steps and landing on 25 mm thick bed of cement mortar 1:1 (1Cement:1Sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of kota tiles. complete in all respect as per the direction of Engineer-in-Charge.	55.41	sqm	608.10	33,697.77
12	Providing checkered tiles on rise, trade etc including cost of tiles, conveyance & royalty of all materials etc complete in all respect as per the direction of Engineer-in-Charge.	9.99	sqm	460.90	4,602.89

*V. Srinivas*

*[Signature]*

S. No.	Description	Quantity	Unit	Rate(in Rs)	Amount in Rs.
13	Supplying, fitting & fixing of Stainless Steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design complete in all respect as per the direction of Engineer-in-Charge.	63.87	Kg	278.00	17,756.94
14	Weather coats over one coat primer to the outer walls including cost of primer, and paint, scaffolding and staging including cost of conveyance, materials etc complete in all respect as per the direction of Engineer-in-Charge.	138.62	Sqm	95.70	13,266.27
15	Wall painting two coats with emulsion paint coat(1st quality) over one coat primer of approved make on even finished surface over a coat of primer with water bond cement primer in all heights with all scaffolding and staging charges including cost, conveyance, taxes of all materials, complete in all respect as per the direction of Engineer-in-Charge.	129.60	Sqm	101.40	13,140.98
16	Providing two coat of enamel paint over one coat of primer including cost of paint and primer of all materials and labour etc. complete in all respect as per the direction of Engineer-in-Charge.	23.97	sqm	94.40	2,262.60
				<b>TOTAL</b>	<b>5,77,347.00</b>

**(Rupees Five Lakh Seventy Seven Thousand Three Hundred Forty Seven)only**

Numer of Items 16 (Sixteen)

My/ Our quoted rate is ..... % (both in figure and words) excess over/ less than / equal to the above estimated cost.

REMARKS:- TENDER RATE QUOTED EXCESS THEN THE ABOVE TENDER AMOUNT WILL NOT BE ACCEPTED

**NB:**

- 1 The Contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate is mentioned, the tender is liable for refection.
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words so there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
- 5 The percentage quoted in the tender without mentioning excess or less will be treated as excess.
- 6 The contractor will write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal point, the first decimal point shall only be considered.

Signature of Contractor

  
**District Project Coordinator**  
**RTE-SSA, Koraput**