

**OFFICE OF THE DIVISIONAL FOREST OFFICER-CUM-
WILDLIFE WARDEN, KORAPUT FOREST DIVISION, KORAPUT**

କୋରାପୁଟ ବନଖଣ୍ଡ ଅଧିକାରୀ ଓ ବନ୍ୟପ୍ରାଣୀ ତତ୍ତ୍ୱାବଧାରକ କାର୍ଯ୍ୟାଳୟ

ଦୂରଭାଷ ନଂ. 06852-251270, ଫ୍ୟାକ୍ସ ନଂ. 06852-25270, ଇ. ମେଲ- ID-dfokoraput@rediffmail.com &

ଅଭିଯୋଗ କର (SMS) ନଂ. 9437011270

Letter No. 3301 /1F-Accts- /2020 Date: 01/07/2021

To

The Deputy Director,
Information and Public Relation Department. (Advertisement)
& Deputy Secretary to Govt. of Odisha,
Information and Public Relation Department,
Odisha, Bhubaneswar.

Sub:

Publication of Advertisement for tender Call Notice for construction of civil work at Koraput during the year, 2021-22.

Sir,

Enclosed, please find herewith the copy of advertisement for construction of civil work at Koraput during the year, 2021-22 both in hard and soft copy. It is requested to kindly make necessary arrangement for publication in two leading Odia News Papers. Further I would request you to kindly supply the complementary copy of the News Papers containing the said advertisement to the undersigned for necessary action at this level and reference.

Encl : As above.

Yours Faithfully,


Divisional Forest Officer
Koraput Forest Division.



GOVERNMENT OF ODISHA
FOREST & ENVIRONMENT DEPARTMENT

COVER – I

TECHNICAL BID DOCUMENTS / DETAILED TENDER CALL NOTICE FOR THE WORK

“Construction of Civil Work at Koraput during the year 2021-22”

Approximate Estimated Cost Put To Tender: **Rs.1,65,73,000 /-**

OFFICE OF THE DIVISIONAL FOREST OFFICER
KORAPUT FOREST DIVISION, KORAPUT

[E-Mail id- koraputdivision@gmail.com](mailto:koraputdivision@gmail.com)

3. Bid documents consisting of plans, specifications, the schedule of quantities and the set of terms & Conditions of contract and other necessary Documents can be seen in the website www.koraput.nic.in
4. The Bid documents will be available in the website: www.koraput.nic.in from **01.07.2021 up to 02.08.2021** for offline bidding.
5. Bids shall be received only on "Offline" on or before **05:00 PM dated 02.08.2021**.
6. The Original Documents only through Regd./Speed post should reach on or before dated **02.08.2021 up to 05:00PM** and other means of posting are not allowed.
7. Technical Bids received offline shall be opened at **11:00AM** on dated **03.08.2021** in the Office in the undersigned in presence of the Bidders who is to attend. Bidders who participated in the Bid can witness the opening of Bids.
8. The cost of Bid documents in shape of Demand draft / Bankers cheque issued from postal pledged and any Nationalized commercial Bank may be prepared in the name of the Divisional Forest Officer, Koraput Forest Division, Koraput mentioned under column No. 6 above payable of Koraput separately i.e. towards paper cost for each Bid respectively.
9. Additional Performance Security shall be often from the Bidder when the Bid amount less then estimated cost put to tender. In such an event only the successful Bidder who has quoted less Bid price rates then the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as Additional Performance Security (APS) in shape of Demand draft / Term Deposit received pledged in favour of the Divisional Forest Officer, Koraput Forest Division within seven days otherwise the Bid shall be canceled and the security deposit shall be forfeited. Further proceeding for black listing shall be initiated against the Bidder.
10. If the rate quote by the Bidder is less than 15% of the tender amount. Then such a Bid shall be rejected and tender shall be finalized basing on merits of the rest Bids, but if more than 1 bid is quoted at 14.99% (Decimals up to 2 Nos. will be taken for all practical purposes) less than estimated cost, the tender accepting authority will finalized the tender through a transparent lottery system. Where all Bidders/ they are authorized representatives, the concerned Divisional Forest Officer and committee will remain present.
11. Other details can be seen in the Biding documents.
12. Any undertaking for any required documents should not be allowed, the tender will be rejected at the spot.
13. The estimated cost is included GST 12%.
14. The cost of labour cess @Rs.1% over and above the work value.
15. Valid and up to date required document should be enclosed falling which the concerned tender paper of the Bidder will be canceled without any further correspondence.
16. The Authority reserves the right to cancel any or all the Bids without assigning any reasons thereof.


Divisional Forest Officer,
Koraput Forest Division.



APPLICATION – TECHNICAL BID

1. Name of Tendering Civil Work
Address (Block Letter) :
2. Name of the Proprietor/ Partner/
Director :
3. Full Address of Registered Office
Proof of Address to be furnished :
4. Address for correspondence
(If other than two) :
5. Contact No. and E-Mail ID of Authorized
Officer/Person :
6. Banker of the Civil Work
(Copy of last Three years transaction) :
7. PAN No. (please furnish document) :
8. GST details (please furnish document) :
9. Works Department License :
10. Labour Department License :
11. Contractor Registration No.
(Please furnish document) :
12. Experience as a contractor
(Proof of experience to be enclosed) :
13. Company Profile :
14. Income tax returns of the company/
Firms for the last three years
(Copies) :
15. Balance sheet last three years
(Copies) :
16. Experience as Civil Contractor in Koraput District:
(Proof of experience to be enclosed)
17. Aadhar Card No. (Xerox copy) :

Certified that the information as above is true to be best of my knowledge & I will be held responsible if anything to the Contrary/ Adverse will be observed in future.

Full Name of Applicant/Authorized Person

Full Signature of Applicant/Authorized Person

Date –
Place -

TENDER SCHEDULE FOR THE WORK

"Construction of Range Office Building at Lamtaput in Lamtaput Forest Range of Koraput Forest Division"

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in all kinds of soil within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & levelling bed etc complete as directed by the Engineer-in-Charges.	71.12 Cum	100 Cum	18454.75	13125.02
02.	Providing and laying sand in foundation and plinth filling with Sand in 9" thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in-Charges.	63.31 Cum	One Cum	611.38	38706.44
03.	Cement Concrete of proportion (1:4:8) in foundation and floors using 4cm (3/2") size Clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	63.31 Cum	One Cum	4381.02	277362.38
04.	Cement Concrete of proportion (1:2:4) in foundation and floors using 12mm (1/2") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	0.32 Cum	One Cum	6101.43	1952.46

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted
B. Manasa

Forest Range Officer,
Lamtaput Range


Divisional Forest Officer,
Koraput Forest Division

05.	R.C.C. Work of M-20 grade with 20mm and down grade black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC - 21 - 1987 and IS - 456 - 1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and Shuttering for R.C.C. Work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete				
	Column Footing	7.75 Cum	1Cum	5173.86	40097.42
	Grade Beam	6.42 Cum	1Cum	5537.79	35552.61
	Column Superstructure & Beam	9.28 Cum	1Cum	10650.45	98836.18
	Lintel Bend	3.21 Cum	1Cum	8666.43	27819.24
	Roof Slab	17.55 Cum	1Cum	9051.69	158857.16
	Chajja	0.34 Cum	1Cum	11843.07	4026.64
06.	Supplying fitting and placing uncoated High Yield Strength Deformed Bar Reinforcement complete as per drawing and technical specification and placing in proper position as required for R.C.C. Work including cost, conveyance, taxes of Steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	51.65 Qntl	One Qntl	8032.17	414861.58
07.	2.5cm (1") thick Grading Concrete over roof slab in Cement Concrete (1:2:2) 6mm (1/4") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	131.21 Sqm	One Sqm	295.15	38726.63
08.	Fly Ash Brick Masonry work in cement mortar (1:6) in Foundation and Plinth using Fly Ash brick of 9" size having crushing strength not less than 75Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	26.56 Cum	One Cum	4301.63	114251.29

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted

 Forest Range Officer,
 Lamtaput Range


Divisional Forest Officer,
 Koraput Forest Division

9.	Fly Ash Brick Masonry work in cement mortar (1:6) in Superstructure using Fly Ash brick of 9" size having crushing strength not less than 75 Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	59.46 Cum	One Cum	4471.27	265861.71
10.	12mm (1/2") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	282.36 Sqm	One Sqm	139.19	39301.69
11.	16mm (5/8") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	650.65 Sqm	One Sqm	197.70	128633.51
12.	Providing & fixing of Floor Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shade including rubbing and polishing as per the design & drawing with cost of all materials, labour, conveyance, taxes, T&P etc. complete as per the direction of Engineering -in-charge.	103.60 Sqm	One Sqm	993.05	102879.98
13.	Supplying, fitting and fixing in position 6.5-6.7mm thick Wall Tiles in dadoes in all floors at all heights and riser of steps with application of 12 mm thick cement mortar of (1:3) in proper slop and filling the gaps with white cement and colouring the surface with silicon paint finished as per the design & drawing with all cost of materials, labour, conveyance, taxes T&P and complete as per the direction of the Engineer-in-charge.	78.39 Sqm	One Sqm	1045.61	81965.37

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted

 Forest Range Officer,
 Lamtaput Range


Divisional Forest Officer,
 Koraput Forest Division

14.	Manufacturing and Supplying of M.S. Door, Window, Ventilator and Grill Gate made up all round angular frame size 35x35x5mm, Door and Window angular frame size 25x25x3/5mm with 20 gage C.R. Sheet supporting flat size 25x8mm and 18x5mm including fitting of clamp, hinges, tower bolt, aldrops including all cost, conveyance tax of materials and labour with T&P required for the work etc complete	1237.05	Kg	One Kg	69.50	85974.98
15.	Labour Charges for fitting and fixing of M.S. Door, Window, Grill Gate and Grills including all cost of Labour with T&P required for the work etc complete.	33.12	Sqm	One Sqm	393.02	13016.82
16.	Painting Two Coats (Enamel Paint) with any approved shade on New Iron Door and windows over a coat of Primer Paint including all cost, conveyance, tax of materials and labour with T&P required for the work etc complete.	79.70	Sqm	One Sqm	184.30	14688.71
17.	Providing & Painting with two coats to the entire outside surface with Weather Coat of any approved make to the outer surface after scraping and cleaning the surface over one coat of Water Bound Wall Primer including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	282.36	Sqm	One Sqm	164.35	46405.87
18.	Providing & Painting with two coats to the entire inside surface with Interior Paint of any approved make to the inner surface after scraping and cleaning the surface over one coat of Cement based putty including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	754.25	Sqm	One Sqm	169.27	127671.90
ELECTRICAL INSTALLATION						
19.	Surface wiring to light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metalic PVC flexible conduit with 5Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories					

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted

 Forest Range Officer,
 Lamtaput Range

Divisional Forest Officer,
Koraput Forest Division

	and connection as per direction of Engineer in Charge. (Make of wire Finolex/ L&T/ Anchor/Havels/V Guard).				
	Short Point	21.00 Nos	1No	416.96	8756.16
	Medium Point	22.00 Nos	1No	641.50	14113.00
	Long Point	2.00 Nos	1No	922.87	1845.74
20.	Surface wiring to submain in FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with 1x1.5sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as equired.(Make of wire Finolex/L&T/Anchor/Havels/V Guard)				
	2x1.50Sqmm PVC Wire	138.50 Mtrs	1Mtr	125.92	17439.92
	2x2.50Sqmm PVC Wire	69.25 Mtrs	1Mtr	164.92	11420.71
	2x4.0Sqmm PVC Wire	30.00 Mtrs	1Mtr	189.25	5677.50
21.	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic covr for the MCB knobs detachable gland plate, interconnections, hosphatized and powder painted including earthing etc. as required (But without MCB/ RCCB/ Isolator) 2 + 4 WAY	4.00 Nos	1No	1636.74	6546.96
22.	Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangment and watering pipe etc with charcoal and salt as required	1.00 Nos	1No	2803.81	2803.81
23.	Installation, Testing and Commissioning of pre-wired fluorescent fitting / compact fluorescent fitting of all sizes complete with all accessories and tube etc. directly on ceiling wall, including connection with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor and earthing as required.	13.00 Nos	1No	116.78	1518.14
24	Installation, Testing and Commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq.mm FR PVC insulated single core multiatrand copper conductor etc. as required.	9.00 Nos	1No	131.16	1180.44
25	25W LED Tube Light	13.00 Nos	1No	557.00	7241.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor


Submitted
BamangaForest Range Officer,
Lamtapat RangeDivisional Forest Officer,
Koraput Forest Division

26	Fan	9.00	Nos	1No	2258.00	20322.00
27	18W LED Ball Lamp	4.00	Nos	1No	450.00	1800.00
GPH & SANITARY						
28	Supplying all materials, labour with T&P for Fixing water closet, squatting pan (Indian type W.C pan) conforming to IS 2556 : Part 3-2004 duly embedded in cement concrete (1:4:8) using hard granite metal 4cm nominal size all complete as per specification (excluding cost of Earth Work in trenches)	1.00	Nos	1No	2903.11	2903.11
29	Providing and fixing on wall face unplasticised-PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including all cost, conveyance of materials and labour with T&P required for the work etc complete as per direction of Engineer in Charge					
	(i) 110mm dia Door Tee	1.00	Nos	1No	299.09	299.09
	(ii) 110mm dia Bend/Tee	1.00	Nos	1No	284.23	284.23
	(iii) 110mm dia Cowl	1.00	Nos	1No	162.33	162.33
	(iv) 110mm dia Noni Trap	1.00	Nos	1No	162.33	162.33
	(v) 110mm dia Socket	5.00	Nos	1No	128.97	644.85
30	Providing and fixing on wall face unplasticised Rigid PVC soil, waste and rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes					
	(i) 90mm dia PVC Pipe	6.00	Mtrs	1Mtr	366.55	2199.29
	(ii) 110mm dia PVC Pipe	15.00	Mtrs	1Mtr	436.08	6541.18
31	Providing and fixing to wall or ceiling and floor pvc pipes class conforming to ASTM-D-1785/89 (Sch-80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor all complete as per specification complete. (excluding cost of Earth Work in trenches)					
	(ii) 25mm dia PVC Pipe	30.00	Mtrs	1Mtr	220.79	6623.64
	(iii) 20mm dia PVC Pipe	30.00	Mtrs	1Mtr	167.86	5035.74
32	Supplying and Fixing of Brass Screw-down Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete.	4.00	Nos	One No	627.65	2510.61
33	Supplying and Fixing of Brass or Gun Metal Full Way Valve conforming to IS:781-1995 of the	1.00	Nos	One No	675.13	675.13

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted


Divisional Forest Officer,
 Koraput Forest Division

Forest Range Officer,
 Lamtaput Range

	following nominal sizes with wheel as per specification complete. - 25mm dia Get Valve				
34	Supplying and Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge - 1000 Ltr PVC Tank	1.00 Nos	One No	11624.90	11624.90
				Total Value of Work	2310907.40
				Or Say	2310907.00
35	Add 1% towards Labour Cess				23109.00
				Total	2334016.00
36	Add 6% towards CGST				140041.00
37	Add 6% towards SGST				140041.00
				Total Amount put to Tender	2614098.00

*My/Our Quoted Rate% (.....
Percent) Excess over / Less then/ Equal to the above
 estimated cost.*

Signature of the Contractor


NOTES:-

01. *The Contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate is mentioned, the tender is liable for rejection.*
02. *Strike out which are not applicable.*
03. *Percentage quoted by the Contractor shall be accurately filled in figures and words, so there is no discrepancy.*
04. *If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the Contractor in words shall be taken as correct.*
05. *The percentage quoted in the tender without mentioning excess or less will be treated as excess.*
06. *The Contractor will write percentage excess or less up to two decimal points only. If he writes the percentage excess or less up to three or more decimal points, the first two decimal points shall only be considered without rounding off.*

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted

Forest Range Officer,
Lamtapat Range

*Divisional Forest Officer,
 Koraput Forest Division*

TENDER SCHEDULE FOR THE WORK

"Construction of Forester Quarter at Nandapur in Semiliguda Forest Range of Koraput Forest Division"

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in all kinds of soil within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & levelling bed etc complete as directed by the Engineer-in-Charges.	55.20 Cum	100 Cum	18454.75	10187.00
02.	Providing and laying sand in foundation and plinth filling with Sand in 9" thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in-Charges.	38.69 Cum	One Cum	631.62	24437.00
03.	Cement Concrete of proportion (1:4:8) in foundation and floors using 4cm (3/2") size Clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	14.43 Cum	One Cum	4272.67	61655.00
04.	Cement Concrete of proportion (1:2:4) in foundation and floors using 12mm (1/2") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding	0.32 Cum	One Cum	6025.88	1928.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.				
05.	R.C.C. Work of M-20 grade with 20mm and down grade black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC - 21 - 1987 and IS - 456 - 1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and Shuttering for R.C.C. Work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete				
	Column Footing	6.03 Cum	1Cum	5102.23	30766.00
	Grade Beam	4.36 Cum	1Cum	5466.16	23832.00
	Column Superstructure & Beam	6.58 Cum	1Cum	10578.82	69609.00
	Lintel Bend	2.17 Cum	1Cum	8594.80	18651.00
	Roof Slab	11.51 Cum	1Cum	8980.06	103360.00
	Chajja	0.48 Cum	1Cum	11771.44	5650.00
06.	Supplying fitting and placing uncoated High Yield Strength Deformed Bar Reinforcement complete as per drawing and technical specification and placing in proper position as required for R.C.C. Work including cost, conveyance, taxes of Steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	36.08 Qntl	One Qntl	8049.06	290410.00
07.	2.5cm (1") thick Grading Concrete over roof slab in Cement Concrete (1:2:2) 6mm (1/4") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	82.92 Sqm	One Sqm	294.87	24451.00
08.	Fly Ash Brick Masonry work in cement motor (1:6) in Foundation and Plinth using Fly Ash brick of 9"	20.49 Cum	One Cum	4249.57	87074.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	size having crushing strength not less than 75Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.				
09.	Fly Ash Brick Masonry work in cement mortar (1:6) in Superstructure using Fly Ash brick of 9" size having crushing strength not less than 75 Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	41.92 Cum	One Cum	4419.21	185253.00
10.	12mm (½") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	248.73 Sqm	One Sqm	140.08	34842.00
11.	16mm (5/8") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	232.38 Sqm	One Sqm	198.76	46188.00
12.	Providing & fixing of Floor Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shade including rubbing and polishing as per the design & drawing with cost of all materials, labour, conveyance, taxes, T&P etc. complete as per the direction of Engineering -in-charge.	60.63 Sqm	One Sqm	1002.03	60753.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

13.	Supplying, fitting and fixing in position 6.5-6.7mm thick Wall Tiles in dadoes in all floors at all heights and riser of steps with application of 12 mm thick cement mortar of (1:3) in proper slop and filling the gaps with white cement and colouring the surface with silicon paint finished as per the design & drawing with all cost of materials, labour, conveyance, taxes T&P and complete as per the direction of the Engineer-in-charge.	16.39 Sqm	One Sqm	1052.34	17248.00
14.	Manufacturing and Supplying of M.S. Door, Window, Ventilator and Grill Gate made up all round angular frame size 35x35x5mm, Door and Window angular frame size 25x25x3/5mm with 20 gage C.R. Sheet supporting flat size 25x8mm and 18x5mm including fitting of clamp, hinges, tower bolt, aldrops including all cost, conveyance tax of materials and labour with T&P required for the work etc complete	1178.66 Kg	One Kg	69.50	81917.00
15.	Labour Charges for fitting and fixing of M.S. Door, Window, Grill Gate and Grills including all cost of Labour with T&P required for the work etc complete.	30.90 Sqm	One Sqm	393.02	12144.00
16.	Painting Two Coats (Enamel Paint) with any approved shade on New Iron Door and windows over a coat of Primer Paint including all cost, conveyance, tax of materials and labour with T&P required for the work etc complete.	76.37 Sqm	One Sqm	184.30	14075.00
17.	Providing & Painting with two coats to the entire outside surface with Weather Coat of any approved make to the outer surface after scraping and cleaning the surface over one coat of Water Bound Wall Primer including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	248.73 Sqm	One Sqm	164.35	40879.00
18.	Providing & Painting with two coats to the entire inside surface with Interior Paint of any approved make to the inner surface after scraping and cleaning the surface over one coat of Cement based putty	293.01 Sqm	One Sqm	169.27	49598.00

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.				
	ELECTRICAL INSTALLATION				
19.	Surface wiring to light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front Bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection as per direction of Engineer in Charge. (Make of wire Finolex/ L&T/ Anchor/Havells/V Guard).				
	Short Point	4.00 Nos	1No	416.96	1668.00
	Medium Point	22.00 Nos	1No	641.50	14113.00
	Long Point	1.00 Nos	1No	922.87	923.00
20.	Surface wiring to submain in FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with 1x1.5sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as equired.(Make of wire Finolex/L&T/Anchor/Havells/V Guard)				
	2x1.50Sqmm PVC Wire	91.50 Mtrs	1Mtr	125.92	11522.00
	2x2.50Sqmm PVC Wire	45.75 Mtrs	1Mtr	164.92	7545.00
	2x4.0Sqmm PVC Wire	30.00 Mtrs	1Mtr	189.25	5678.00
21.	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic covr for the MCB knobs detachable gland plate, interconnections, hosphatized and powder painted including earthing etc. as required (But with out MCB/	4.00 Nos	1No	1636.74	6547.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

	RCCB/ Isolator) 2 + 4 WAY				
22.	Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc with charcoal and salt as required	1.00 Nos	1No	2803.81	2804.00
	GPH & SANITARY				
23.	Supplying all materials, labour with T&P for Fixing water closet, squatting pan (Indian type W.C pan) conforming to IS 2556 : Part 3-2004 duly embedded in cement concrete (1:4:8) using hard granite metal 4cm nominal size all complete as per specification (excluding cost of Earth Work in trenches)	1.00 Nos	1No	2904.29	2904.00
24.	Providing and fixing on wall face unplasticised-PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including all cost, conveyance of materials and labour with T&P required for the work etc complete as per direction of Engineer in Charge				
	(i) 110mm dia Door Tee	1.00 Nos	1No	299.09	299.00
	(ii) 110mm dia Bend/Tee	1.00 Nos	1No	284.23	284.00
	(iii) 110mm dia Cowl	1.00 Nos	1No	162.33	162.00
	(iv) 110mm dia Noni Trap	1.00 Nos	1No	162.33	162.00
	(v) 110mm dia Socket	5.00 Nos	1No	128.97	645.00
25.	Providing and fixing on wall face unplasticised Rigid PVC soil, waste and rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
	(i) 90mm dia PVC Pipe	6.00 Mtrs	1Mtr	366.55	2199.00
	(ii) 110mm dia PVC Pipe	15.00 Mtrs	1Mtr	436.08	6541.00
26.	Providing and fixing to wall or ceiling and floor pvc pipes class conforming to ASTM-D-1785/89 (Sch-80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor all complete as per specification complete. (excluding cost of Earth Work in trenches)				

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

	(ii) 25mm dia PVC Pipe	30.00 Mtrs	1Mtr	220.79	6624.00
	(iii) 20mm dia PVC Pipe	30.00 Mtrs	1Mtr	167.86	5036.00
27	Supplying and Fixing of Brass Screw-down Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete.	4.00 Nos	One No	627.65	2511.00
26.	Supplying and Fixing of Brass or Gun Metal Full Way Valve conforming to IS:781-1995 of the following nominal sizes with wheel as per specification complete. - 25mm dia Get Valve	1.00 Nos	One No	675.13	675.00
28.	Supplying and Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge - 1000 Ltr PVC Tank	1.00 Nos	One No	11624.90	11625.00
29	Provision of gound leveling/ site clearance/ sign board and unforeseen items	L/S			42000.00
				Total	1427374.00
				Total Value of Work	1427374.00
29.	Add 1% towards Labour Cess				13854.00
				Total	1441228.00
30.	Add 6% towards CGST				86474.00
31.	Add 6% towards SGST				86474.00
				Total Amount in Rs.	1614174.00
				Or limited to Rs.	1613900.00
				Total Amount put to Tender	1613900.00


**My/Our Quoted Rate% (.....
Percent) Excess over / Less then/ Equal to the above
 estimated cost.**

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

**Divisional Forest Officer,
 Korapat Forest Division**

Seethamma

 Forest Range Officer
 Semiliguda Forest Range

TENDER SCHEDULE FOR THE WORK

"Construction of Forest Guard Quarter at Kasandi, Nandapur Section in Semiliguda Forest Range of Koraput Forest Division"

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in all kinds of soil within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & levelling bed etc complete as directed by the Engineer-in-Charges.	49.80 Cum	100 Cum	18454.75	9190.00
02.	Providing and laying sand in foundation and plinth filling with Sand in 9" thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in-Charges.	21.03 Cum	One Cum	661.98	13921.00
03.	Cement Concrete of proportion (1:4:8) in foundation and floors using 4cm (3/2") size Clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	11.98 Cum	One Cum	4366.65	52312.00
04.	Cement Concrete of proportion (1:2:4) in foundation and floors using 12mm (1/2") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of	0.32 Cum	One Cum	6124.71	1960.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

	materials and labour with T&P required for the work etc complete.					
05.	R.C.C. Work of M-20 grade with 20mm and down grade black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC - 21 - 1987 and IS - 456 - 1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and Shuttering for R.C.C. Work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete					
	Column Footing	5.16	Cum	1Cum	5202.66	26846.00
	Grade Beam	2.93	Cum	1Cum	5566.59	16310.00
	Column Superstructure & Beam	4.83	Cum	1Cum	10679.25	51581.00
	Lintel Bend	1.91	Cum	1Cum	8695.23	16608.00
	Roof Slab	8.65	Cum	1Cum	9080.49	78546.24
	Chajja	0.39	Cum	1Cum	11871.87	4630.00
06.	Supplying fitting and placing uncoated High Yield Strength Deformed Bar Reinforcement complete as per drawing and technical specification and placing in proper position as required for R.C.C. Work including cost, conveyance, taxes of Steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	27.48	Qntl	One Qntl	8056.01	221379.00
07.	2.5cm (1") thick Grading Concrete over roof slab in Cement Concrete (1:2:2) 6mm (1/4") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	82.92	Sqm	One Sqm	297.36	24657.00
08.	Fly Ash Brick Masonry work in cement motor (1:6) in Foundation and Plinth using Fly Ash brick of 9" size having crushing strength not less than 75Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering	16.56	Cum	One Cum	4315.84	71470.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	and curing etc complete as per direction of Engineer-in-Charges.				
09.	Fly Ash Brick Masonry work in cement mortar (1:6) in Superstructure using Fly Ash brick of 9" size having crushing strength not less than 75 Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	30.97 Cum	One Cum	4485.48	138915.00
10.	12mm (½") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	125.91 Sqm	One Sqm	140.76	17723.00
11.	16mm (5/8") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	206.26 Sqm	One Sqm	199.60	41169.00
12.	Providing & fixing of Floor Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shade including rubbing and polishing as per the design & drawing with cost of all materials, labour, conveyance, taxes, T&P etc. complete as per the direction of Engineering -in-charge.	45.29 Sqm	One Sqm	1006.01	45562.00
13.	Supplying, fitting and fixing in position 6.5-6.7mm thick Wall Tiles in dadoes in all floors at all heights and riser of steps with application of 12 mm thick cement mortar of (1:3) in proper slop and filling the gaps with white cement and	16.87 Sqm	One Sqm	1055.44	17805.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	colouring the surface with silicon paint finished as per the design & drawing with all cost of materials, labour, conveyance, taxes T&P and complete as per the direction of the Engineer-in-charge.				
14.	Manufacturing and Supplying of M.S. Door, Window, Ventilator and Grill Gate made up all round angular frame size 35x35x5mm, Door and Window angular frame size 25x25x3/5mm with 20 gage C.R. Sheet supporting flat size 25x8mm and 18x5mm including fitting of clamp, hinges, tower bolt, aldrops including all cost, conveyance tax of materials and labour with T&P required for the work etc complete	873.43 Kg	One Kg	69.50	60703.00
15.	Labour Charges for fitting and fixing of M.S. Door, Window, Grill Gate and Grills including all cost of Labour with T&P required for the work etc complete.	23.07 Sqm	One Sqm	393.02	9067.00
16.	Painting Two Coats (Enamel Paint) with any approved shade on New Iron Door and windows over a coat of Primer Paint including all cost, conveyance, tax of materials and labour with T&P required for the work etc complete.	56.54 Sqm	One Sqm	184.30	10420.00
17.	Providing & Painting with two coats to the entire outside surface with Weather Coat of any approved make to the outer surface after scraping and cleaning the surface over one coat of Water Bound Wall Primer including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	125.91 Sqm	One Sqm	164.35	20693.00
18.	Providing & Painting with two coats to the entire inside surface with Interior Paint of any approved make to the inner surface after scraping and cleaning the surface over one coat of Cement based putty including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	251.55 Sqm	One Sqm	169.27	42580.00
	ELECTRICAL INSTALLATION				
19.	Surface wiring to light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC				

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metalic PVC flexible conduit with 5Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge. (Make of wire Finolex/ L&T/ Anchor/Havels/V Guard).				
	Short Point	9.00 Nos	1No	416.96	3753.00
	Medium Point	6.00 Nos	1No	641.50	3849.00
	Long Point	1.00 Nos	1No	922.87	923.00
20.	Surface wiring to submain in FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metalic heavy duty flexible conduit 1.6 mm thick along with 1x1.5sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as equired.(Make of wire Finolex/L&T/Anchor/Havels/V Guard)				
	2x1.50Sqmm PVC Wire	48.00 Mtrs	1Mtr	125.92	6044.00
	2x2.50Sqmm PVC Wire	24.00 Mtrs	1Mtr	164.92	3958.00
	2x4.0Sqmm PVC Wire	15.00 Mtrs	1Mtr	189.25	2839.00
21.	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic covr for the MCB knobs detachable gland plate, interconnections, hosphatized and powder painted including earthing etc. as required (But with out MCB/ RCCB/ Isolator) 2 + 4 WAY	2.00 Nos	1No	1636.74	3273.00
22.	Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangment and watering pipe etc with charcoal and salt as required	1.00 Nos	1No	2803.81	2804.00
	GPH & SANITARY				

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

23.	Supplying all materials, labour with T&P for Fixing water closet, squatting pan (Indian type W.C pan) conforming to IS 2556 : Part 3-2004 duly embedded in cement concrete (1:4:8) using hard granite metal 4cm nominal size all complete as per specification (excluding cost of Earth Work in trenches)	1.00 Nos	1No	2906.06	2906.00
24.	Providing and fixing on wall face unplasticised-PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including all cost, conveyance of materials and labour with T&P required for the work etc complete as per direction of Engineer in Charge				
	(i) 110mm dia Door Tee	1.00 Nos	1No	299.09	299.00
	(ii) 110mm dia Bend/Tee	1.00 Nos	1No	284.23	284.00
	(iii) 110mm dia Cowl	1.00 Nos	1No	162.33	162.00
	(iv) 110mm dia Noni Trap	1.00 Nos	1No	162.33	162.00
	(v) 110mm dia Socket	5.00 Nos	1No	128.97	645.00
25.	Providing and fixing on wall face unplasticised Rigid PVC soil, waste and rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
	(i) 90mm dia PVC Pipe	6.00 Mtrs	1Mtr	366.55	2199.00
	(ii) 110mm dia PVC Pipe	6.00 Mtrs	1Mtr	436.08	2616.00
26.	Providing and fixing to wall or ceiling and floor pvc pipes class conforming to ASTM-D-1785/89 (Sch-80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor all complete as per specification complete. (excluding cost of Earth Work in trenches)				
	(ii) 25mm dia PVC Pipe	15.00 Mtrs	1Mtr	220.79	3312.00
	(iii) 20mm dia PVC Pipe	15.00 Mtrs	1Mtr	167.86	2518.00
27.	Supplying and Fixing of Brass Screw-down Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete.	3.00 Nos	One No	627.65	1883.00

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

26.	Supplying and Fixing of Brass or Gun Metal Full Way Valve conforming to IS:781-1995 of the following nominal sizes with wheel as per specification complete. - 25mm dia Get Valve	1.00 Nos	One No	675.13	675.00
28.	Supplying and Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge - 1000 Ltr. PVC Tank	1.00 Nos	One No	11624.90	11625.00
29	Provision for ground leveling/ site clearance/ sign board and unforeseen items	L/S			14000.00
				Total	1064776.00
				Total Value of Work	1064776.00
30.	Add 1% towards Labour Cess				10508.00
				Total	1075284.00
31.	Add 6% towards CGST				64517.00
32.	Add 6% towards SGST				64517.00
				Total Amount in Rs.	1204318.00
				Or limited to Rs.	1204000.00
				Total Amount put to Tender	1204000.00

My/Our Quoted Rate% (.....
Percent) Excess over / Less then/ Equal to the above
 estimated cost.

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
 Koraput Forest Division

Submitted


 Forest Range Officer
 Semiliguda Forest Range

TENDER SCHEDULE FOR THE WORK

"Construction of Forest Guard Quarter at Balda Section in Balda Forest Range of Koraput Forest Division"

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in all kinds of soil within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & levelling bed etc complete as directed by the Engineer-in-Charges.	49.80 Cum	100 Cum	18454.75	9190.00
02.	Providing and laying sand in foundation and plinth filling with Sand in 9" thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in-Charges.	21.03 Cum	One Cum	631.62	13283.00
03.	Cement Concrete of proportion (1:4:8) in foundation and floors using 4cm (3/2") size Clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	11.98 Cum	One Cum	4319.70	51750.00
04.	Cement Concrete of proportion (1:2:4) in foundation and floors using 12mm (1/2") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	0.32 Cum	One Cum	6077.63	1945.00
05.	R.C.C. Work of M-20 grade with 20mm and down grade black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC - 21 -				

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	1987 and IS - 456 - 1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and Shuttering for R.C.C. Work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete				
	Column Footing	5.16 Cum	1Cum	5155.12	26600.00
	Grade Beam	2.93 Cum	1Cum	5519.05	16171.00
	Column Superstructure & Beam	4.83 Cum	1Cum	10631.71	51351.00
	Lintel Bend	1.91 Cum	1Cum	8647.69	16517.00
	Roof Slab	8.65 Cum	1Cum	9032.95	78135.00
	Chajja	0.39 Cum	1Cum	11824.33	4611.00
06.	Supplying fitting and placing uncoated High Yield Strength Deformed Bar Reinforcement complete as per drawing and technical specification and placing in proper position as required for R.C.C. Work including cost, conveyance, taxes of Steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	27.48 Qntl	One Qntl	8054.03	221325.00
07.	2.5cm (1") thick Grading Concrete over roof slab in Cement Concrete (1:2:2) 6mm (1/4") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	82.92 Sqm	One Sqm	296.13	24555.00
08.	Fly Ash Brick Masonry work in cement motor (1:6) in Foundation and Plinth using Fly Ash brick of 9" size having crushing strength not less than 75Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	16.56 Cum	One Cum	4290.84	71056.00
09.	Fly Ash Brick Masonry work in cement motor (1:6) in Superstructure using Fly Ash brick of 9" size having crushing strength not less than 75 Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	30.97 Cum	One Cum	4460.48	138141.00
10.	12mm (1/2") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and	125.91 Sqm	One Sqm	140.25	17659.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.				
11.	16mm (5/8") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	206.26 Sqm	One Sqm	198.98	41042.00
12.	Providing & fixing of Floor Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shade including rubbing and polishing as per the design & drawing with cost of all materials, labour, conveyance, taxes, T&P etc. complete as per the direction of Engineering -in-charge.	45.29 Sqm	One Sqm	1004.60	45498.00
13.	Supplying, fitting and fixing in position 6.5-6.7mm thick Wall Tiles in dados in all floors at all heights and riser of steps with application of 12 mm thick cement mortar of (1:3) in proper slop and filling the gaps with white cement and colouring the surface with silicon paint finished as per the design & drawing with all cost of materials, labour, conveyance, taxes T&P and complete as per the direction of the Engineer-in-charge.	16.87 Sqm	One Sqm	1054.23	17785.00
14.	Manufacturing and Supplying of M.S. Door, Window, Ventilator and Grill Gate made up all round angular frame size 35x35x5mm, Door and Window angular frame size 25x25x3/5mm with 20 gage C.R. Sheet supporting flat size 25x8mm and 18x5mm including fitting of clamp, hinges, tower bolt, aldrops including all cost, conveyance tax of materials and labour with T&P required for the work etc. complete	873.43 Kg	One Kg	69.50	60703.00
15.	Labour Charges for fitting and fixing of M.S. Door, Window, Grill Gate and Grills including all cost of Labour with T&P required for the work etc complete.	23.07 Sqm	One Sqm	393.02	9067.00
16.	Painting Two Coats (Enamel Paint) with any approved shade on New Iron Door and windows over a coat of Primer Paint including all cost, conveyance, tax of materials and labour with T&P required for the work etc complete.	56.54 Sqm	One Sqm	184.30	10420.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

17.	Providing & Painting with two coats to the entire outside surface with Weather Coat of any approved make to the outer surface after scraping and cleaning the surface over one coat of Water Bound Wall Primer including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	125.91 Sqm	One Sqm	164.35	20693.00
18.	Providing & Painting with two coats to the entire inside surface with Interior Paint of any approved make to the inner surface after scraping and cleaning the surface over one coat of Cement based putty including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	251.55 Sqm	One Sqm	169.27	42580.00
ELECTRICAL INSTALLATION					
19.	Surface wiring to light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size, MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection as per direction of Engineer in Charge. (Make of wire Finolex/ L&T/ Anchor/Havels/V Guard).				
	Short Point	9.00 Nos	1No	416.96	3753.00
	Medium Point	6.00 Nos	1No	641.50	3849.00
	Long Point	1.00 Nos	1No	922.87	923.00
20.	Surface wiring to submain in FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with 1x1.5sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as Required.(Make of wire Finolex/L&T/Anchor/Havels/V Guard)				
	2x1.50Sqmm PVC Wire	48.00 Mtrs	1Mtr	125.92	6044.00
	2x2.50Sqmm PVC Wire	24.00 Mtrs	1Mtr	164.92	3958.00
	2x4.0Sqmm PVC Wire	15.00 Mtrs	1Mtr	189.25	2839.00
21.	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic covr for the MCB knobs detachable gland plate, interconnections,	2.00 Nos	1No	1636.74	3273.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

	hosphatized and powder painted including earthing etc. as required (But without MCB/ RCCB/ Isolator) 2 + 4 WAY				
22.	Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc with charcoal and salt as required	1.00 Nos	1No	2803.81	2804.00
GPH & SANITARY					
23.	Supplying all materials, labour with T&P for Fixing water closet, squatting pan (Indian type W.C pan) conforming to IS 2556 : Part 3-2004 duly embedded in cement concrete (1:4:8) using hard granite metal 4cm nominal size all complete as per specification (excluding cost of Earth Work in trenches)	1.00 Nos	1No	2904.29	2904.00
24.	Providing and fixing on wall face unplasticised-PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including all cost, conveyance of materials and labour with T&P required for the work etc complete as per direction of Engineer in Charge				
	(i) 110mm dia Door Tee	1.00 Nos	1No	299.09	299.00
	(ii) 110mm dia Bend/Tee	1.00 Nos	1No	284.23	284.00
	(iii) 110mm dia Cowl	1.00 Nos	1No	162.33	162.00
	(iv) 110mm dia Noni Trap	1.00 Nos	1No	162.33	162.00
	(v) 110mm dia Socket	5.00 Nos	1No	128.97	645.00
25.	Providing and fixing on wall face unplasticised Rigid PVC soil, waste and rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
	(i) 90mm dia PVC Pipe	6.00 Mtrs	1Mtr	366.55	2199.00
	(ii) 110mm dia PVC Pipe	6.00 Mtrs	1Mtr	436.08	2616.00
26.	Providing and fixing to wall or ceiling and floor pvc pipes class conforming to ASTM-D-1785/89 (Sch-80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor all complete as per specification complete. (excluding cost of Earth Work in trenches)				
	(ii) 25mm dia PVC Pipe	15.00 Mtrs	1Mtr	220.79	3312.00
	(iii) 20mm dia PVC Pipe	15.00 Mtrs	1Mtr	167.86	2518.00
27.	Supplying and Fixing of Brass Screw-down Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete.	3.00 Nos	One No	627.65	1883.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

28.	Supplying and Fixing of Brass or Gun Metal Full Way Valve conforming to IS:781-1995 of the following nominal sizes with wheel as per specification complete. - 25mm dia Get Valve	1.00 Nos	One No	675.13	675.00
29.	Supplying and Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge - 1000 Ltr PVC Tank	1.00 Nos	One No	11624.90	11625.00
29	Provision for ground leveling/ site clearance/ sign board and unforeseen items	L/S			18000.00
				Total:-	1064804.00
				Total Value of Work	1064804.00
30.	Add 1% towards Labour Cess				10468.00
				Total	1075272.00
31.	Add 6% towards CGST				64516.00
32.	Add 6% towards SGST				64516.00
				Total Amount in Rs.	1204304.00
				Or limited to Rs.	1204000.00
				Total Amount put to Tender	1204000.00

My/Our Quoted Rate% (.....

.....Percent) Excess over / Less than/ Equal to the above estimated cost.

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

Submitted

[Signature]
Range Officer
Balda Forest Range

TENDER SCHEDULE FOR THE WORK

**"Construction of Forest Guard Quarter at Guneipada BIT in Machakunda Section
under Lamtaput Forest Range of Koraput Forest Division"**

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in all kinds of soil within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & levelling bed etc complete as directed by the Engineer-in-Charges.	49.80 Cum	100 Cum	18454.75	9190.47
02.	Providing and laying sand in foundation and plinth filling with Sand in 9" thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in-Charges.	21.03 Cum	One Cum	560.78	11793.19
03.	Cement Concrete of proportion (1:4:8) in foundation and floors using 4cm (3/2") size Clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	11.98 Cum	One Cum	4368.37	52333.07
04.	Cement Concrete of proportion (1:2:4) in foundation and floors using 12mm (1/2") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour	0.32 Cum	One Cum	6146.23	1966.79

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted
Bamaale

Divisional Forest Officer,
Koraput Forest Division


**Forest Range Officer,
Lamtaput Range**

	with T&P required for the work etc complete.				
05.	R.C.C. Work of M-20 grade with 20mm and down grade black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC - 21 - 1987 and IS - 456 - 1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and Shuttering for R.C.C. Work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete				
	Column Footing	5.16 Cum	1Cum	5227.18	26972.25
	Grade Beam	2.93 Cum	1Cum	5591.11	16381.95
	Column Superstructure & Beam	4.83 Cum	1Cum	10703.77	51699.21
	Lintel Bend	1.91 Cum	1Cum	8719.75	16654.72
	Roof Slab	8.65 Cum	1Cum	9105.01	78758.34
	Chajja	0.39 Cum	1Cum	11896.39	4639.59
06.	Supplying fitting and placing uncoated High Yield Strength Deformed Bar Reinforcement complete as per drawing and technical specification and placing in proper position as required for R.C.C. Work including cost, conveyance, taxes of Steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	27.48 Qntl	One Qntl	8068.95	221734.75
07.	2.5cm (1") thick Grading Concrete over roof slab in Cement Concrete (1:2:2) 6mm (1/4") size Clean hard black crusher broken granite Chips of approved quality from approved quarry including hosting lowering and laying in layers ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete.	82.92 Sqm	One Sqm	297.67	24682.80
08.	Fly Ash Brick Masonry work in cement mortar (1:6) in Foundation and Plinth using Fly Ash brick of 9" size having crushing strength not less than 75Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	16.56 Cum	One Cum	4257.67	70507.02

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted

 Forest Range Officer,
 Lamtaput Range

Divisional Forest Officer,
 Koraput Forest Division

	Fly Ash Brick Masonry work in cement mortar (1:6) in Superstructure using Fly Ash brick of 9" size having crushing strength not less than 75 Kg per Sq. Cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc complete as per direction of Engineer-in-Charges.	30.97 Cum	One Cum	4427.31	137113.79
10.	12mm (½") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	125.91 Sqm	One Sqm	139.68	17587.11
11.	16mm (5/8") thick Cement Plaster in C.M. (1:6) finished smooth to brick walls after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, Scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc complete in all respect in all floors as per direction of Engineer-in-Charges.	206.26 Sqm	One Sqm	198.30	40901.36
12.	Providing & fixing of Floor Tiles in floors treads or steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigments to match the shade including rubbing and polishing as per the design & drawing with cost of all materials, labour, conveyance, taxes, T&P etc. complete as per the direction of Engineering -in-charge.	45.29 Sqm	One Sqm	1011.36	45804.49
13.	Supplying, fitting and fixing in position 6.5-6.7mm thick Wall Tiles in dadoes in all floors at all heights and riser of steps with application of 12 mm thick cement mortar of (1:3) in proper slop and filling the gaps with white cement and colouring the surface with silicon paint finished as per the design & drawing with all cost of materials, labour, conveyance, taxes T&P and complete as per the direction of the Engineer-in-	16.87 Sqm	One Sqm	1058.82	17862.29

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted
Bemange

Divisional Forest Officer,
Koraput Forest DivisionForest Range Officer,
Lantaput Range

	charge.				
14.	Manufacturing and Supplying of M.S. Door, Window, Ventilator and Grill Gate made up all round angular frame size 35x35x5mm, Door and Window angular frame size 25x25x3/5mm with 20 gage C.R. Sheet supporting flat size 25x8mm and 18x5mm including fitting of clamp, hinges, tower bolt, aldrops including all cost, conveyance tax of materials and labour with T&P required for the work etc complete	873.43 Kg	One Kg	69.50	60703.39
15.	Labour Charges for fitting and fixing of M.S. Door, Window, Grill Gate and Grills including all cost of Labour with T&P required for the work etc complete.	23.07 Sqm	One Sqm	393.02	9066.97
16.	Painting Two Coats (Enamel Paint) with any approved shade on New Iron Door and windows over a coat of Primer Paint including all cost, conveyance, tax of materials and labour with T&P required for the work etc complete.	56.54 Sqm	One Sqm	184.30	10420.32
17.	Providing & Painting with two coats to the entire outside surface with Weather Coat of any approved make to the outer surface after scraping and cleaning the surface over one coat of Water Bound Wall Primer including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	125.91 Sqm	One Sqm	164.35	20693.31
18.	Providing & Painting with two coats to the entire inside surface with Interior Paint of any approved make to the inner surface after scraping and cleaning the surface over one coat of Cement based putty including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer-in-charge.	251.55 Sqm	One Sqm	169.27	42579.87
	ELECTRICAL INSTALLATION				
19.	Surface wiring to light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metalic PVC flexible conduit with 5Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite				

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted
SamaForest Range Officer,
Lantaput RangeDivisional Forest Officer,
Koraput Forest Division

	cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge. (Make of wire Finolex/ L&T/ Anchor/Havels/V Guard).				
	Short Point	9.00 Nos	1No	416.96	3752.64
	Medium Point	6.00 Nos	1No	641.50	3849.00
	Long Point	1.00 Nos	1No	922.87	922.87
20.	Surface wiring to submain in FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm thick along with 1x1.5sq.mm FR PVC insulated single core multistrand copper conductor as earth wire as equired.(Make of wire Finolex/L&T/Anchor/Havels/V Guard)				
	2x1.50Sqmm PVC Wire	48.00 Mtrs	1Mtr	125.92	6044.16
	2x2.50Sqmm PVC Wire	24.00 Mtrs	1Mtr	164.92	3958.08
	2x4.0Sqmm PVC Wire	15.00 Mtrs	1Mtr	189.25	2838.75
21.	Supply and fixing of following way single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 V on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic covr for the MCB knobs detachable gland plate, interconnections, hosphatized and powder painted including earthing etc. as required (But with out MCB/ RCCB/ Isolator) 2 + 4 WAY	2.00 Nos	1No	1636.74	3273.48
22.	Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangment and watering pipe etc with charcoal and salt as required	1.00 Nos	1No	2803.81	2803.81
	GPH & SANITARY				
23.	Supplying all materials, labour with T&P for Fixing water closet, squatting pan (Indian type W.C pan) conforming to IS 2556 : Part 3-2004 duly embedded in cement concrete (1:4:8) using hard granite metal 4cm nominal size all complete as per specification (excluding cost of Earth Work in trenches)	1.00 Nos	1No	2900.18	2900.18

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor


Divisional Forest Officer,
Koraput Forest DivisionSubmitted
BamaForest Range Officer,
Lamtaput Range

24.	Providing and fixing on wall face unplasticised-PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including all cost, conveyance of materials and labour with T&P required for the work etc complete as per direction of Engineer in Charge				
	(i) 110mm dia Door Tee	1.00 Nos	1No	299.09	299.09
	(ii) 110mm dia Bend/Tee	1.00 Nos	1No	284.23	284.23
	(iii) 110mm dia Cowl	1.00 Nos	1No	162.33	162.33
	(iv) 110mm dia Noni Trap	1.00 Nos	1No	162.33	162.33
	(v) 110mm dia Socket	5.00 Nos	1No	128.97	644.85
25.	Providing and fixing on wall face unplasticised Rigid PVC soil, waste and rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
	(i) 90mm dia PVC Pipe	6.00 Mtrs	1Mtr	366.55	2199.29
	(ii) 110mm dia PVC Pipe	6.00 Mtrs	1Mtr	436.08	2616.47
26.	Providing and fixing to wall or ceiling and floor pvc pipes class conforming to ASTM-D-1785/89 (Sch-80) and pipe fittings of the following nominal bore with clamps including making good the wall, ceiling and floor all complete as per specification complete. (excluding cost of Earth Work in trenches)				
	(ii) 25mm dia PVC Pipe	15.00 Mtrs	1Mtr	220.79	3311.82
	(iii) 20mm dia PVC Pipe	15.00 Mtrs	1Mtr	167.86	2517.87
27.	Supplying and Fixing of Brass Screw-down Bib Cocks (Taps) polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete.	3.00 Nos	One No	627.65	1882.95
28.	Supplying and Fixing of Brass or Gun Metal Full Way Valve conforming to IS:781-1995 of the following nominal sizes with wheel as per specification complete. - 25mm dia Get Valve	1.00 Nos	One No	675.13	675.13
29.	Supplying and Fixing Rotational moulded polyethylene cylindrical vertical water storage tanks conforming to IS : 12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra	1.00 Nos	One No	11624.90	11624.90

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Submitted

 Forest Range Officer,
 Lamtaput Range

 Divisional Forest Officer,
 Koraput Forest Division

	sockets and jam nuts, fixing ball valve etc, including hoisting upto a height of 5 metres above ground level and placing the tank to the required position etc all complete as per specification and direction of the Engineer in charge - 1000 Ltr PVC Tank				
		Total Value of Work			1046771.28
				Or Say	1046771.00
29.	Add 1% towards Labour Cess				10468.00
				Total	1057239.00
30.	Add 6% towards CGST				63434.00
31.	Add 6% towards SGST				63434.00
		Total Amount put to Tender			1184107.00

*My/Our Quoted Rate% (.....
Percent) Excess over / Less then/ Equal to the above
 estimated cost.*

Signature of the Contractor

NOTES:-

01. The Contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate is mentioned, the tender is liable for rejection.
02. Strike out which are not applicable.
03. Percentage quoted by the Contractor shall be accurately filled in figures and words, so there is no discrepancy.
04. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the Contractor in words shall be taken as correct.
05. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
06. The Contractor will write percentage excess or less up to two decimal points only. If he writes the percentage excess or less up to three or more decimal points, the first two decimal points shall only be considered without rounding off.

For Official Use Only:


- | | | |
|---------------------------------|---|--|
| 01. Bid Cost | : | Furnished / Not Furnished. |
| 02. Bid Security | : | Furnished / Not Furnished. |
| 03. Valid License | : | Attested Copy Furnished / Not Furnished. |
| 04. Pan Card | : | Attested Copy Furnished / Not Furnished. |
| 05. GST Certificate | : | Attested Copy Furnished / Not Furnished. |
| 06. Affidavit | : | Furnished / Not Furnished. |
| 07. No Relationship Certificate | : | Furnished / Not Furnished. |

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

Submitted

**Forest Range Officer,
Lamtaput Range**

NO RELATIONSHIP CERTIFICATE

01. Certified that I am/we are not related to any officers of Forest Department of rank of Range Officer and above, any officer of the rank of Asst. Secretary and above in the Forest and Environment Department and I am/ We are also aware that the facts subsequently proved to be false my/our contract will be rescind with forfeiture of E. M. D. and total security deposit and I/We shall be liable to make good the loss or damage resulting from such cancellation.

I/We also note that non-submission of this certificate with the tender will render my/our tender liable for rejection.

Signature of the Contractor

Signature of the Contractor

No. Of correction:.....

No. Of overwriting.....

Submitted
Sarnaga

**Forest Range Officer,
Lamtapat Range**

*Divisional Forest Officer,
Koraput Forest Division*

TENDER SCHEDULE FOR THE WORK

“Construction of Causeway at Nageswary forest road in
Balda forest range of Koraput forest Division”

SI No	Item Of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in hard soil within 50 meter initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm. to 7cm and laying in layer not exceeding 0.03 Mtr in depth & leveling bed etc. complete as directed by the engineer-in-Charges.	2.77Cum	100Cum	18454.75	511.00
02.	Provideing and laying sand in foundation and plinth filling with sand in 9" thick layers of approved quality free from dust, dirt and other foreign material to proper line and grade, watering and ramming etc. complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of engineer- in- charges	7.82Cum	One Cum	631.62	4939.00
03	C.C of proportion (1:3:6) in foundation and floors using 4cm (3/2") size clean hard black hand broken granite metal of approved quality from approved quarry including hosting lowering and lying in layers not exceeding15cm (6') thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete				

No Of Correction.....

No of overweighting.....

Signature of the Contractor

Divisional Forest officer,
Koraput Forest Division

TENDER SCHEDULE FOR THE WORK

“Construction of Causeway at Permanent Nursery In Balda forest range of Koraput forest Division”

SI No	Item Of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in excavation of foundation in hard soil within 50 meter initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm. to 7cm and laying in layer not exceeding 0.03 Mtr in depth & leveling bed etc. complete as directed by the engineer-in-Charges.	2.77Cum	100Cum	18454.75	511.00
02.	Provideing and laying sand in foundation and plinth filling with sand in 9" thick layers of approved quality free from dust, dirt and other foreign material to proper line and grade, watering and ramming etc. complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of engineer- in- charges	7.82Cum	One Cum	631.62	4939.00
03	C.C of proportion (1:3:6) in foundation and floors using 4cm (3/2") size clean hard black hand broken granite metal of approved quality from approved quarry including hosting lowering and lying in layers not exceeding15cm (6') thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete				

No Of Correction.....

No of overweighting.....

Signature of the Contractor

Divisional Forest officer,
Koraput Forest Division

	A) Sub- Structure	10.48Cum	One Cum	4700.64	49263.00
	(B) Super Structure	2.66Cum	One Cum	4856.61	12919.00
04	C.C of proportion(1:2:4) in foundation and floors using 12mm (1/2") size clean hard black crusher broken granite chips of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm(6") thick to the required level, ramming watering and curing etc complete including all cost conveyance, tax and royalties of materials and labour with T&P required for the work etc complete.	4.11Cum	One Cum	6077.63	24979.00
05	Earth work in excavationof hard soil with in 50M initially lead and 1.50M initial lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03M in depth & leveling the bed as directed by the engineer-in charges including cost of royalty etc complete.	4.94Cum	One 100Cum	15378.96	760.00
28	Cost of other unforeseen items only				340.00
29	Cost of labours cess @Rs.1% over and above the work value				934
30	Cost of SGST @6% over and above the work value				5679.00
31	Cost of CGST @6% over and above the work value				5679.00
				Grand Total	106003.00
				Limited to	106000.00
				Total Amount put to tender	106000.00

My/Our Quoted Rate.....% (..... Percent)
Excess over/ Less then/ Equal to the above estimated cost.

No Of Correction.....
No of overweighting.....

Signature of the Contractor

Divisional Forest officer,
Koraput Forest Division

Submitted
Range Officer
Balda Forest Range

(7)

TENDER SCHEDULE FOR THE WORK

Construction Of Boundary Wall To Forester Quarter At Machkund Section In Lamtaput Forest Range Of Koraput Forest Division

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil in foundation within 50M initially lead and 1.50M initially lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.03Mtr in depth & leveling bed etc complete as directed by the Engineer-in-charges.	43.98 Cum	100 Cum	184.54	8116.00
2	Providing and laying sand in foundation and plinth filling with sand in 9 thick layers of approved quality free from dust, dirt and other foreign materials to proper line and grade, watering and ramming etc complete with all lead, lifts de-lifts including labour charges with cost, conveyance, tax and royalty of all materials, labour, T&P and other incidental charges etc complete as per direction of Engineer-in – Charges.	4.02 Cum	One Cum	368.5	1481.00
3	Cement Concrete in Proportion (1:4:8) in foundation and floors using 4cm (3/2") size clean hard black crusher broken granite metal of approved quality from approved quarry including hosting lowering and laying in layers not exceeding 15cm (6") thick to the required level, ramming watering and curing etc complete including all cost, conveyance, taxes and royalties of materials and labour with T&P required for the work etc complete	8.04 Cum	One Cum	4164.16	33480.00
4	Fly Ash Brick Masonry work in cement mortar (1:6) in foundation and plinth using fly ash brick of 9" size having crushing strength not less than 35kg per sq.cm. including splays cutting , circular molding, chamfering and corbelling, watering and curing etc. complete as per direction of Engineer-in-charge.	23.92 Cum	One Cum	4128.34	98750.00
5	R.C.C work of M-25 grade with 20mm and down grde black hard granite crusher broken chips of 150mm cubes at 28days using minimum quality of cement as per clause 003.5 of IRC -21-1987 and IS- 456-1987 with clean crusher broken hard granite chips of 20mm. to 10mm including watering and curing, Centering and shuttering for R.C.C work, Cost, conveyance, tax and royalty of all materials and labour with T&P required for the work etc complete				
a	Column base & Footing	5.67 Cum	One Cum	4993.45	28313.00
b	Plinth beam	6.59Cum	One Cum	5357.38	35305.00
c	Column in S/S	2.70cum	One Cum	10470.04	28269.00
d	Lintel bend	2.15 Cum	One Cum	8486.02	18245.00
6	Supplying fitting and placing uncoated HYSD Bar reinforcement complete as per drawing and technical specification and placing in proper position as required for RCC work including cost , conveyance, taxes of steel and cost of binding wire 18 to 20 gauge and labour with T& P required for the work etc. complete in all respect in all floors as per direction of Engineer-in-charges.	16.21 Qntl	One Qntl	8105.47	131390.00

No. of Correction.....

No. of overwriting.....

Signature of the Contractor


Submittal
Banerjee Divisional Forest Officer,
Koraput Forest Division.
Forest Range Officer,
Lamtaput Range

7	Fly Ash Brick Masonry work in cement mortar (1:6) in foundation and plinth using fly ash brick of 9" size having crushing strength not less than 35 Kg per sq. cm. including splays cutting, circular molding, chamfering and corbelling, watering and curing etc. complete as per direction of engineer-in-charges.	32.10 Cum	One Cum	4297.98	137965.00
8	12mm thick cement plaster in cement mortar (1:6) over brick work after raking out joints cleaning & finishing the plaster surface smooth including watering and curing, scaffolding screening sand etc complete with cost, conveyance, taxes and royalties of all materials and labour with T&P required for the work etc. complete in all respect in all floors as per direction of Engineer-in Charges.	403.95 Sqm	One Sqm	137.67	55612.00
9	Finishing walls with water providing cement paint of approved shade on new work two coat to give an even shade over a coat of Cement Washing over the wall surface including all cost of materials, scaffolding, labour, watering & curing T&P etc complete as per direction of Engineer- in charge-	403.95 Sqm	One Sqm	50.59	20436.00
				Sub total	597362.00
10	Labour Cess 1%				5974.00
11	GST (SGST- 6% & CGST-6%)				72400.00
				Grand Total	675736.00
				Limited to Rupees	675000.00

My/ Our Quoted rate _____ % (_____ Pcent) Excess over/ Less then/ Equal to the above estimated cost.

No. of Correction.....
No. of overwriting.....

Signature of the Contractor

Submitted

Forest Range Officer,
Lamtapat Range

Divisional Forest Officer,
Koraput Forest Division.

TENDER SCHEDULE FOR THE WORK

"Construction of Eco Resort at Deomali (Kotiya) in Semiliguda Forest Range of Koraput Forest Division"

Sl. No.	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
01.	Earth work in hard soil of gravelly soil within 50M initial lead and 1.50M initial lifts including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.30Mtr in depth & leveling bed etc complete as directed by the Engineer-in-Charges.	184.58 Cum	100 Cum	19392.80	35795.00
02.	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance, royalty and other taxes including watered and ramming with all leads, lifts and compaction etc. complete in all respect as per specification and direction of Engineer-in-Charges.	80.39 Cum	100 Cum	104526.90	84029.00
03.	CC (1:3:6) using 4cm size CBG Metal of approved quality quarried and free from weathered skin and foreign materials including mixing the materials and laying the concrete in layers not exceeding 0.15m in depth to required level curing ramming, finishing, etc, with all leads, lifts and delifts complete in all respect to proper profile and level including dewatering if necessary and cost, conveyance, royalty and other taxes etc. complete as directed by the Engineer-in-charge.	66.93 Cum	One Cum	4228.70	283027.00
04.	RR hard granite stone masonry in CM (1:6) from approved quarry in T&P with cost, conveyance, royalty & taxes of all materials to work site with all leads, lifts & delifts including watering and curing with all labour T&P required for the work etc. complete as directed by the	43.30 Cum	One Cum	3041.80	131710.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	Engineer-in-charge.				
05.	Bricks work with CB Bricks 23cm x 11cm x 8cm size with CM (1:6) with single scaffolding including cost of materials, required etc. complete in all respect including cost, conveyance, royalty and other taxes of all materials with supply of labour and T&P required in all respect as directed by the Engineer-in-charge.				
	Ground Floor	54.28 Cum	1Cum	3966.20	215285.00
	1ST Floor	48.46 Cum	1Cum	4189.70	203033.00
06.	Cement concrete (1:2:4) with 12mm size hard granite CB chips etc. complete				
	Ground Floor (Plinth Protection)	4.14 Cum	1Cum	5356.80	22177.00
07.	RCC work of M-20 grade with 20mm and down grade black hard granite CB stone chips including hoisting and laying				
	Column base (Ground Floor)	36.34 Cum	1Cum	4550.90	165380.00
	Columns (Ground Floor)	11.23 Cum	1Cum	9438.20	105991.00
	Columns (1ST Floor)	4.21 Cum	1Cum	10512.90	44259.00
	Plinth Beam (Ground Floor)	7.62 Cum	1Cum	4861.60	37045.00
	Lintel (Ground Floor)	4.13 Cum	1Cum	7567.50	31254.00
	Lintel (1ST Floor)	3.15 Cum	1Cum	8268.00	26044.00
	Chajjas (Ground Floor)	0.84 Cum	1Cum	10689.80	8979.00
	Chajjas (1ST Floor)	0.40 Cum	1Cum	12014.70	4806.00
	Roof Beam (Ground Floor)	9.14 Cum	1Cum	9438.20	86265.00
	Roof Beam (1ST Floor)	6.53 Cum	1Cum	10512.90	68649.00
	Stair Slabs (Ground Floor)	1.58 Cum	1Cum	7753.30	12250.00
	Slabs (Ground Floor)	30.01 Cum	1Cum	8123.90	243798.00
	Slabs (1ST Floor)	19.90 Cum	1Cum	8935.70	177820.00
08.	Labour fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification				
	Ground Floor	111.12 Qtl.	1Qtl.	6418.50	713224.00
	1ST Floor	36.91 Qtl.	1Qtl.	6438.40	237641.00
09.	2.5cm thick Grading Concrete over roof slab in Cement Concrete (1:2:2) with 6mm size hard granite crusher broken Chips on new work.				
	Ground Floor	52.33 Sqm	1 Sqm	258.90	13548.00
	1ST Floor	159.25 Sqm	1 Sqm	282.40	44972.00
10.	12mm thick cement plaster (1:6) for brick work				
	Ground floor (Outside walls)	183.15 Sqm	1 Sqm	126.80	23223.00
	1ST Floor (Outside walls)	218.28 Sqm	1 Sqm	131.40	28682.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

Divisional Forest Officer,
Koraput Forest Division

11.	16mm thick cement plaster (1:6) for brick work				
	Ground floor (Inside walls)	544.48 Sqm	1 Sqm	178.50	97190.00
	1ST Floor (Inside walls)	399.48 Sqm	1Sqm	182.70	62023.00
12.	20mm thick Cement Plaster with C.M. (1:6) over stone masonry work with all cost, conveyance, taxes and royalties with all leads, lifts and delifts to work site including watering, curing, etc. complete in all respect as per direction of Engineer-in-Charges.	50.17 Sqm	1Sqm	189.00	9482.00
13.	Labour for fixing of M.S. Grill's, Door, Window etc.				
	Ground floor (Inside walls)	17.91 Sqm	1 Sqm	67.23	1204.00
	1ST Floor (Inside walls)	7.70 Sqm	1Sqm	67.23	518.00
14.	Cost of MS Grill's, window (Farm & Grill) including T.C to be paid as per EPM rate				
	Ground floor	537.30 Kgs	1 Kg	68.50	36805.00
	1ST Floor	231.00 Kgs	1 Kg	68.50	15824.00
15.	Providing fitting, fixing of Al. Door with anodized Al. Door section 9202 as vertical member, 9201 as bottom and middle member with frame section as 9221 with tapered clip No.4660 and the frame to be completed by means of jointing angle No. 1855 including all cost of labour, T&P hire charges of drilling machine, labour charges etc. complete excluding cost of laminated board.				
	Ground floor	292.90 Kgs	1 Kg	368.50	107933.00
	1ST Floor	217.66 Kgs	1 Kg	368.50	80209.00
16.	Providing fitting, fixing up window (Sliding type) made up Alumunium section 9778, as window frame section No. 4095,4096 and 9777,3994 as sutter frame with 5mm thick black glass as pannel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes of labour, T&P etc. complete as per direction of E.I.C				
	Ground floor	87.49 Kgs	1 Kg	505.90	44261.00
	1ST Floor	37.61 Kgs	1 Kg	505.90	19029.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

17.	Cost of 5mm Black Glass (I.S.I)				
	Ground floor	17.91 Sqm	1 Sqm	552.34	9892.00
	1ST Floor	7.90 Sqm	1Sqm	552.34	4253.00
18.	Cost of 12mm Prelaminated particle board (Standard type) (I.S.I)				
	Ground floor	21.00 Sqm	1Sqm	589.79	12386.00
	1ST Floor	17.00 Sqm	1Sqm	589.79	10026.00
19.	Supplying, fitting & fixing vetrifed Tiles in floors of size 600mm x 600mm of approved make conforming to ISI:13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 Course sand) and filling joints with white cement of approved quality including cost of all materials, labour, conveyance, taxes , T&P etc. required for the work all complete as per the direction of Engineering -in-charge.				
	Ground floor	207.19 Sqm	1Sqm	778.70	161339.00
	1ST Floor	116.67 Sqm	1Sqm	786.90	91808.00
20.	Fixing vetrifed tiles in dadoes skirting and risers steps on 12mm thick cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including polishing complete ecluding cost of precast tiles.				
	Ground floor	158.36 Sqm	1 Sqm	860.50	136269.00
	1ST Floor	138.83 Sqm	1Sqm	873.00	121199.00
21.	Providing, fitting and fixing of suspended decorative false ceiling with 12.50mm thick GYP board of approved quality etc and complete as per the direction of the Engineer-in-charge.				
	Ground floor	167.10 Sqm	1 Sqm	1162.90	194321.00
	1ST Floor	132.81 Sqm	1Sqm	1162.90	154445.00
22.	Finishing wall surface with cement based wall putty (water based) of approved make and finish smooth and even surface to receive painting including all cost, conveyance tax of materials and labour with T&P required for the work etc complete				

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

	Ground floor (In side Area)	818.46 Sqm	1 Sqm	56.20	45997.00
	1ST Floor	299.75 Sqm	1Sqm	58.10	17415.00
23.	Wall painting two coats with weather coat of approved shade to outer side finished area over one coat of water bound cement primer including cost, T.C etc. of paint & primer per the direction of the Engineer-in-charge.				
	Ground floor	233.32 Sqm	1 Sqm	114.70	26762.00
	1ST Floor	235.85 Sqm	1Sqm	119.00	28066.00
24.	Wall painting two coats with plastic emulsion paint of approved shade over one coat of water bound cement primer including cost, T.C etc. of paint & primer as per the direction of the Engineer-in-charge.				
	Ground floor	818.46 Sqm	1 Sqm	120.40	98543.00
	1ST Floor	299.75 Sqm	1Sqm	122.90	36839.00
25.	Supplying, fitting affixing of stainless steel of 304 grade on hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm @0.90mtr. C/C and stainless square pipe bracing of size 32mm 32mm x 32mm in 3rows in stair case as per approved design and specification, buffing, polishing etc. with cost conveyance, taxes of all materials labour, T&P etc. required for the complete in all respect.				
	Ground floor	78.59 Kg	1 Kg	246.60	19379.00
	1ST Floor	133.59 Kg	1 Kg	246.60	32944.00
26.	Painting 2 coats with any approved paint on new/ old wood work over one coat of primer including cost, T.C. etc. of paint & primer as per the direction of the Engineer-in-charge.				
	Ground floor	8.97 Sqm	1 Sqm	163.70	1468.00
	1ST Floor	3.85 Sqm	1Sqm	167.80	646.00
		SUB TOTAL:-			47,27,261.00
27.	Provision for Chajja slop design, M.S stair from 1 st floor to 2 nd floor etc.	L/S			70000.00

No. Of correction:.....

No. Of overwriting.....

Signature of the Contractor

*Divisional Forest Officer,
Koraput Forest Division*

28.	Provision for Internal Electrification 8.00%				378189.00
29.	Provision for cost of Water Supply & Sanitation (Internal & External) 10.00%				472736.00
30.	Provision for 4Nos 1.5 ton A.C. with stabilizer wiring fitting and fixing etc.	L/S			200000.00
31.	Provision for Bore well with PVC casing pipe and pipe fittings, Tube well including cost of water tank and all type of fitting.	L/S			150000.00
32.	Provision for leveling of land and protection wall	L/S			300000.00
33.	Provision for Furniture, Door & Window screen etc	L/S			500000.00
34.	Provision for Signboard, steps & other unforeseen items				8745.00
				SUB TOTAL:-	68,06,931.00
35.	Labour Cess. 1%				68,069.00
				SUB TOTAL:-	68,75,000.00
36.	GST (OGST-6% & CGST-6%)				8,25,000.00
				GRAND TOTAL:-	77,00,000.00
				Total Amount put to Tender	77,00,000.00

My/Our Quoted Rate% (.....
Percent) Excess over / Less then/ Equal to the above
 estimated cost.

No. Of correction:.....

No. Of overwriting:.....

Signature of the Contractor

Submitted

17
 Forest Range Officer
 Semiliguda Forest Range

Divisional Forest Officer,
 Koraput Forest Division