

TENDER SCHEDULE

NAME OF THE WOEK :---	CONSTN. OF TWO STOREY STAFF QUARTER WITH ELECTRIFICATION, WATER SUPPLY & SANITATION AT BLOCK COLONY IN BONDHUGAM
SCHEME :--- 3rd SFC / 2013-14	BLOCK:- BONDHUGAM
ETIMATE COST :-- ₹ 3500000/-	G.P:- BANDHUGAON
AMOUNT PUT TO TENDER :-- ₹ 2775084/-	
COST OF TENDER PAPER :- ₹ 6000/-	E.M.D REQUIRED:-- ₹ 27800/-

PERIOD OF COMPLITION:--6 (SIX) MONTHS	CLASS OF CONTRACTOR :--"C" & "B"
----------------------------------------	----------------------------------

Sl.No	Item of Work	Qty.	Unit	Estimated Cost (In Rs)	
				Rate	Amount
1	2	3	4	5	6
1	Earthwork for excavation foundation in hard of soil including stoney earth in foundation with all lifts, delifts and leads including dressing and levelling the bed and depositing excavated earth at place away from work site including dewatering, shuttering, cost of labour, royalty and T&P sundries required for the work etc. complete as per direction of Engineer-in-Charge.	132.62	100 Cum	22414.00	29725.00
2	Supplying and filling in foundation trenches and plinth, ditches with sand well watered and rammed in layers not exceeding 23 cm. in depth with all lead and lift including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, sundries, T&P required for the work etc. complete in all respect as per direction by the Engineer in charge.	20.45	100 Cum	33004.20	6749.00
3	Cement concrete of proportion (1:4:8) in foundation and floors using 4cm size clean hard black crusher broken granite stone metal of approved quality and from approved quarry including hoisting, lowering and laying concrete in layers not exceeding 15 cm. (6") thick to the required level ramming, watering, curing etc. complete including cost, conveyance, royalties and taxes of all materials with all labour and T&P required for the work etc. complete in all respect and as per the direction of the Engineer-in-charge.	26.61	One Cum	4411.50	117390.00
4	Random rubble stone masonry in c.m(1:6) in foundation and plinth by using hard black broken granite stone including bond stones from approved quarry including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering, curing including cost, conveyance, royalties and taxes of all materials with all labour and T & P required for the work complete in all respect as per direction of Engineer-in-Charge.	42.92	One Cum	3382.80	145190.00
5	C.B brick masonry in cement mortar (1:6) in super structure using C.B. Bricks 23cm x 11cm x 8cm size having crushing strength not less than 35Kg/sqcm with dimension tolerance + 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance, royalties and taxes of all materials with all labour and T & P required for the work complete in all respect as per direction of Engineer-in-Charge.				
(A)	GROUND FLOOR	47.01	One Cum	4234.30	199054.00
(B)	1st FLOOR	58.72	One Cum	4499.20	264193.00

1	2	3	4	5	6
6	Cement concrete of prop (1:2:4) with 12 mm size hard granite C.B. chips of approved quality from approved quarry free from weathered skins and foreign materials including hoisting, lowering and laying concrete in layers not exceeding 0.15 mtr. in depth, watering and curing for 21 days etc complete including cost of all materials, conveyance, taxes, cess, royalty of materials with labour, concrete mixer, vibrator, t&p, sundries, for the work etc. complete as per the direction of Engineer-in-charge.				
(A)	GROUND FLOOR	0.54	One Cum	6042.60	3263.00
(B)	1st FLOOR	0.56	One Cum	6343.10	3552.00
7	R.C.C. work of M20 in following works using 12 mm. to 20 mm. (½" to ¾") size (20 mm. not to exceed 25%) hard black crusher broken granite stone chips of approved quality from approved quarry including hoisting, lowering, laying and compacting concrete, watering curing, centering, shuttering and finishing the exposed surfaces smooth with cost, conveyance, royalties, taxes of all materials with all labour and T & P required for the work etc. complete in all respect but excluding the cost and conveyance of M.S. rods or Tor steel and binding wire of 18 to 20 gauge and labour charges for straightening, cutting, bending, binding and tying the grills and placing in proper position and as per the direction of the Engineer-in-charge.				
	GROUND FLOOR				
(A)	Coloumn Base	25.06	One Cum	5069.40	127039.00
(B)	Coloumn	8.28	One Cum	10830.00	89672.00
(C)	Plinth Beam	5.72	One Cum	5433.10	31077.00
(D)	Lintel	3.65	One Cum	8608.40	31421.00
(E)	Chajja	1.08	One Cum	12282.50	13265.00
(F)	Roof Beam and Beams	5.54	One Cum	10830.00	59998.00
(G)	Stair Slab	1.48	One Cum	10315.90	15268.00
(H)	Slab	16.19	One Cum	9267.90	150047.00
	1st FLOOR				
(A)	Coloumn	4.64	One Cum	12274.60	56954.00
(B)	Lintel	3.65	One Cum	9542.00	34828.00
(C)	Chajja	1.08	One Cum	14061.20	15186.00
(D)	Roof Beam and Beams	5.54	One Cum	12274.60	68001.00
(E)	Stair Slab	1.53	One Cum	11642.20	17813.00
(F)	Slab	17.69	One Cum	10353.20	183148.00
8	Providing, Cutting, straightening coiled or bent up M.S. Rod or tor steel of primary steel producers such as SAIL / Tiscon / RINL (grade Fe-500D) etc. including bending, binding, welding and jointing if necessary and tying the grills and placing in position as required for R.C.C. Work and for providing fan hooks as required, hoisting, lowering, laying including cost, conveyances, taxes of M.S. Rod or tor steel and binding wires of 18 to 20 gauge and labour required for the work for bending, binding and tying the grills in all floors (payment will be made on standard weight of B.I.S. for M.S. Rods or tor steel only) etc. complete as per specification & direction of Engineer-in-charge.				
(A)	GROUND FLOOR	66.61	One Qtl.	8067.30	537363.00
(B)	1st FLOOR	36.60	One Qtl.	8091.00	296131.00

1	2	3	4	5	6
9	Providing 2.5cm thick Grading Concrete over roof slab with cement concrete (1:2:2) using 6mm size black hard granite crusher broken chips and screened & washed sharp sand for mortar and finished smooth to the rough surface of slab including watering and curing with cost, conveyance, royalties and taxes of all materials with cost of all labour, and T&P required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	4.54	One Sqm.	294.40	1337.00
(B)	1st FLOOR	136.48	One Sqm.	322.20	43974.00
10	Providing 12 mm thick cement plaster with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	145.20	One Sqm.	141.20	20502.00
(B)	1st FLOOR	191.31	One Sqm.	146.70	28065.00
11	Providing 16 mm thick cement plaster with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	412.30	One Sqm.	200.80	82790.00
(B)	1st FLOOR	460.01	One Sqm.	205.70	94624.00
12	Providing 20 mm thick cement plaster over stone work with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	17.25	One Sqm.	211.10	3641.00
13	Labour for fixing of door, window and grills including all concrete works, hold fasts curing etc. complete as per the direction of EIC.				
(A)	GROUND FLOOR	29.27	One Sqm.	67.40	1973.00
(B)	1st FLOOR	27.47	One Sqm.	67.40	1851.00
TOTAL AMOUNT PUT TO TENDER					2775084.00

NUMBER OF ITEMS :- 13 (THIRTEEN)

(Rupees twenty seven lakh seventy five thousand eighty four)Only

REMARKS:-TENDER RATE QUOTED EXCESS THEN THE ABOVE TENDER AMOUNT WILL NOT BE ACCEPTED

PERCENTAGE RATE TO BE QUOTED BY THE TENDERER :-

_____ % LESS

THEN THE ABOVE TENDER AMOUNT PUT TO TENDER

(QUOTE RATE BOTH IN FIGURE & WORDS CLEARLY)

BLOCK DEVELOPMENT OFFICER
BONDHUGAM

SIGNATURE OF THE CONTRACTOR