



GOVERNMENT OF ODISHA

(PANCHAYATIRAJ & DRINKING WATER DEPARTMENT)

OFFICE OF THE PANCHAYAT SAMITI: POTTANGI
DISTRICT-KORAPUT (ODISHA)

TENDER SCHEDULE

1. Name of the work : Construction of 6 Nos. of additional class room in Gangeswari Degree Mahavidyalaya, Pottangi.
2. Name of the scheme : Special Problem Fund 2022-23 (13th Phase)
3. Amount put to tender : Rs. 47,07,333/-
4. E.M.D required : Rs. 47,100/-
5. No. of Items : 21
6. Class of Contractor : B & A
7. Cost of Tender Papers : Rs. 6,000/-
8. Period of Completion : 06 (Six) Months
9. Date of available of tender papers
In the Koraput District website : Dt. 15.09.2023 to Dt. 26.09.2023
10. Last date for receipt of tender papers
through Speed Post/ Registered Post : 26.09.2023 (Up to 05:00 P.M)
11. Date of opening of tender papers : 27.09.2023 at 11:30 A.M)
12. Name of the contractor : _____

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

CHECKLIST TO BE ENSURED BY THE BIDDER

Sl. No.	Particulars	Whether Furnished		Remarks
		YES	NO	
01.	Cost of Tender papers.			
02.	All the EMDs requirements mentioned in the DTCN.			
03	Copy of Valid Contractor's Registration Certificate.			
04.	Copy of Valid GST Registration Certificate and GSTIN.			
05.	Copy of GST Clearance Certificate.			
06.	Copy of I.T.C.C. & PAN Card.			
07.	No Relation Certificate (Annexure-I).			
08. (A)	Information regarding current litigation, debarring / expelling of the tender or abandonment of the work by the tenderer.			
(B)	Affidavit in legal stamp paper for preference, if any.			
09.	Additional Performance Security in case the bid price/rate is less than the estimated cost put to tender.			
10.	Similar nature of work. (Annexure-II)			
11.	Existing commitments & Ongoing Works.			
12.	M.O.U. (Memorandum of Understanding duly Notarized) with eligible registered electrical contractor having valid H.T. / LT/M.V. license).			
13.	Caste Certificate, if any.			
14.	Tender Schedule in support of Financial Bid			


Signature of the Contractor


Block Development officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

DETAILED TENDER CALL NOTICE

1. Sealed tender on percentage rate bids are invited to be eventually drawn in form of the PWD F-2 agreement and will be received up to **Dt. 26.09.2023 (Up to 05:00 PM)** by the B.D.O, Pottangi for the work **"Construction of 6 Nos. of additional class room in Gangeswari Degree Mahavidyalaya, Pottangi"** at the tender amount published vide Tender Call Notice No. **2628** dated. **14.09.2023** from the class of eligible contractors registered with the State Governments and Contractors of equivalent Grade/ Class registered with Central Government/ MES/ Railways/ CPWD and will be opened on **Dt. 27.09.2023 at 11:30 A.M** in presence of the tenderers or their authorized representatives who are requested (By the BDO, Pottangi) to present in the Panchayat Samiti, Pottangi.
2. The tenderer shall please note that, the works shall have to be completed within the time limit given in the Tender Call Notice noted above commencing from the date of issued written order. The Authority for acceptance of tender shall rest absolutely with Tender Committee of Panchayat Samiti, Pottangi.
3. Tenderers are required to pay **EMD @ 1% (One Percent)** of the amount put to tender (rounded up to hundred) as mentioned in the Tender Call Notice in shape of **Term Deposit Receipt** of Nationalized Bank/KBP/NSC/Post Office Time Deposit (Valid for minimum one year from the date of receipt) Post Office Saving Bank Pass Book duly pledged with **BDO, Pottangi** must accompanied the tender, failing which the tenders will be summarily rejected. The Earnest Money to be refunded to the unsuccessful tenderers on application without any interest after acceptance of the tender and the same shall be retained in case of successful tenderers and shall carry no interest.
4. The details of the works including Estimated Cost, Tender Value, EMD required, Class of Contractor, Completion time, Cost of Tender Papers etc. are available in the Koraput District official website **<https://www.koraput.nic.in>**.
5. The BDO, Panchayat Samiti, Pottangi reserves right to reject any or all the tenders received without assigning any reason. The tenders whose tender is selected for acceptance shall be intimated within a period of three days upon written intimation being given to him of acceptance of the tender shall deposit the initials security amount equal to that of EMD and sign the agreement in the percentage rate of contract form of the PWD. The initial security deposit with the earnest money and the amount withheld from successive work bills according to the provision of the percentage rate contract shall be retained as security deposit. Failure to the execute the agreement and required deposit of the security as above shall be entitled for future of the earnest money. No tender shall be finally accepted unless the required amount of security deposit. The written agreement to be entered into between contractor and the BDO, Pottangi shall be the foundation of the right of both the parties and the contract shall be deemed to be complete until the agreement has first bill signed by the contractor and then by the BDO, Pottangi in the manner as laid down in OPWD Code. The BDO, Pottangi shall accept the security deposit in shape of Bank Draft/Cash/NCS etc. drawn in favour of the BDO, Pottangi in any nationalized Bank of the Post Office as the case May be payable at Pottangi. The documents/receipt shall be furnished to the B.D.O., Pottangi.

Signature of the Contractor


Block Development officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

6. Performance Security shall be deposited by the Bidder, If the bidder quoted their rate less than the scheduled amount, they should deposit the less amount i.e., difference between amount quoted by the contractor and the amount put to tender in shape of Demand Draft/ Banker's Cheque of any Nationalized Bank in favour of **B.D.O., Pottangi** along with tender document.
7. The tender of defaulting contractors (leaving the earlier works of Panchayat Samiti, Pottangi incomplete and those contractors whose progress on Panchayat Samiti, Pottangi works are unsatisfactory within the stipulated scheduled period) will not be considered till completion of the earlier works awarded by this Panchayat Samiti, Pottangi.
8. The EMD amount is to be forfeited if the tenderer back out from the offer of acceptance of tender by the competent authority and also intimated to the License Issuing Authority for taking necessary action against them.
9. The work need to commence immediately after award of tender. Penalty of 3% of total tender value will be imposed if work does not commence within one week. The authority reserves the right to award the tender to L2 Bidder (at L1 rate), if the work does not commence with two weeks of awarding the tender.
10. One cover should contain Tender Papers for One Work Only. If tender papers (both separate cover and loose papers) for more than one work are found in a Single Registered Cover, then all the tender documents will be rejected.
11. Both E.M.D. & I.S.D. shall be refunded to the successful tender after 01 year of completion of works provided that all defects if pointed out by Engineering Staff are rectified. However, the security deposit will be refunded only after audit, which is being deducted from time to time in all running as well as final bills.
12. The Percentage Rate shall be quoted in words and figures. Otherwise, the tender will be liable for rejection. In case of discrepancy between words & Figure, the percentage rate quoted in words will be treated as final.
13. The Contractor shall be responsible for payment of royalties or other charges for quarrying materials. All local taxes including state sales tax and income tax, ferry and tollage charges, other local taxes shall be paid by the contractor. The same will be deducted from the work bill if the contractor fails to produce the valid receipt in support of the payment of the above said charges/taxes.
14. The tender shall not be considered unless the tenderer encloses true copies of PAN Card and Sales Tax Clearance Certificate along with his tender and original certificate are to be produced before the B.D.O. Panchayat Samiti, Pottangi at the time of sale of tender papers.
15. If the contractor removes any materials or stock supplied to him from the site of the work with a view to dispose of the same dishonestly or for any other reason without written permission of the B.D.O. Pottangi he shall in addition to any other liabilities civil or criminal arising out of such removal, liable to pay a penalty equivalent to give times rate of the materials or stock so removed according to the stipulated rate and the penalty so imposed shall be recovered from the Contractor from any sum that may then be immediately due or any time there after becomes due to the contractor or from its security.

Signature of the Contractor


Block Development officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput


16. The contractor shall be fully liable to indemnify the Panchayat Samiti's payment of any compensation under workmen compensation Act VIII of 1923 on account of worker employed by him and the full amount of compensation paid shall be recovered from the contractor.
17. Every tenderer must examine the detailed specification of the work before submitting his tender. The right reserved without impairing the contract to make such increase or decrease in the quantities or items of work or deleting any item mentioned in the schedule attached to the tender notice, as may be considered necessary to complete the work fully and satisfactorily. It will definitely be understood that Panchayat Samiti do not accept responsibility for the corrections or completeness of the quantities shown in the schedule. The schedule is liable to alterations, additions and deductions shall in no case invalidate contract and no claim for extra monetary compensation shall be entertained.
18. The length and sizes of M.S. or Tor Rods are to be procured by the contractor and should be SAIL Brand and the same be procured as per the direction of Engineer-in-Charges.
19. All reinforced cement concrete work shall conform to the detailed standard specification and shall be of proportion as per design with the specification mentioned in the tender schedule and mixed in Concrete Mixture, compacted with Vibrator. All times of work shall be executed in accordance with the detailed standard specification of Odisha as followed by State PWD (Roads & Buildings).
20. Shuttering and centering shall be with seasoned Sal wood planks inner wide of which shall be lined with suitable shuttering made leak proof and tight including false work as directed or alternatively steel shuttering and centering shall be used.
21. The selected contractor may take delivery of departmental supply of materials according to his need for the work issued by the Assistant Engineer/ Junior Engineer of the work on written application by the contractor or in the intent from. The contractor shall make all arrangements for storage of materials and pay watchmen etc., shall be borne by him. The Panchayat Samiti, is not responsible at site. Once the materials are issued to the contractor, he shall be responsible for any loss, damage theft etc. till the materials are fully utilized in the work to the full satisfaction of the Assistant Engineer/Junior Engineer. If the contractor stops or slows down the progress of work under any pleas whatever, he shall be liable to pay the full penalty under relevant clause of the item rate contract.
22. For the purpose of the jurisdiction, in the event of dispute if any, the contractor shall be deemed to have been into within the Pottangi Block Area and it is agreed that neither party to the agreement will be competent to bring any suit with regards to the matter covered by this contract at ay place outside Block Development Officer, Pottangi.
23. It is contractor's responsibility to correctly demark lay out and orientation of the building etc. and fixation of level pillars at site as directed by the Asst. Engineer or Junior Engineer. All expenditure in connection with tools and plants, instrumental materials etc., shall be borne by the contractor.
24. After the work is finished, all surplus materials and debris shall be removed, preliminary work such as vat mixing plates etc., are to be dismantled and all the materials removed from the site and ground up to 30mtrs. wide from the building etc. should be cleaned and dressed by the Contractor at is own cost. The net rate quoted should be inclusively of all these expenditures. He should return all the unused Departmental materials to JE concerned.
25. The Contractor shall not interfere with the execution of water supply or electrical fittings and other works entrusted to any other agency by the Panchayat Samiti at the time during the progress of work if the works are not included in the agreement.

Signature of the Contractor


Block Development officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

26. The Engineer-in-Charges of work shall have the right to reject the scaffolding and centering etc., made for the work and such structure if found defective in his/their opinion.
27. The contractor shall at his own cost make water supply for all work and make sanitary arrangements for his labour campus. The Contractors shall also arrange adequate lighting arrangement for night work, wherever at his own cost.
28. Boiling of water arising from any reason whatsoever from the foundation, if necessary, shall be borne by the Contractor. No payment shall be made for fixing arranges bench marks. Level pillars, profiles and benching and levelling the ground whenever required. The rated quoted shall be for finished items of work inclusive of all incidental items of work.
29. All the quantities mentioned in the schedule for building works are combined for ground and multistore floors (in case of multistore building) and the rate shall be throughout the same.
30. Cement Concrete in roof slab, beams, lintels, foundation, abutments, piers etc., wherever prescribed by Engineer-in-Charges shall be executed strictly as per the direction of Engineer-in-Charge.
31. It should be understood clearly that on claim whatsoever shall be entertained as regards extra item of work or extra quantity of any item in excess of the estimate, written order must be obtained from the Block Development Officer, Pottangi for such extra item or quantity of work.
32. The Contractor must follow the fair wages clauses as introduced by the State Government.
33. Except as otherwise provided in the contract, all quotation and disputes relating to the meaning of the specification, designs, drawings and instructions contained therein and as to the quality of workmanship of materials in the work, or as the any other question claim right, matter of anything whatsoever of any arising out of execution of failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof shall be referred to the tender committee. The award of the Tender Committee shall be final, conclusive and binding on all parties to this contract.
34. The Contractors shall arrange at his own cost, necessary tools and plants as may be required for the efficient execution of the work and the rates quoted should be inclusive of the running and hire charges of such tools and plants.
35. The Contractor shall submit to the Panchayat Samiti office monthly return of the labour both skilled and un-skilled employed by him on the work. In case of non-payment, contractor is solely responsible in the labour court.
36. No part of the contract shall be sublet without written permission of the Block Development Officer, Pottangi or transfer to be made by power of attorney authorizing other to receive payment on the contractor's behalf.
37. No tender documents shall be sold to the intending bidder on the date of opening of the tender.
38. If any further necessary information is required the Block Development Officer, Pottangi will furnish such information but it must be in order and according to instructions.
39. Only Ultra Tech/ACC/Konark Brand Cement (OPC-43/53 Grade) will be used and weight of each cement bag being taken as 50Kg. Further that the M.S. or Tor Rod shall be used in the work as per SAIL Brand.
40. No contractor shall be permitted to furnish his tender in his own manuscript papers or latter pads.

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput
Page 6 of 15

41. In the event of delay in the supply of detailed structural designs for unavoidable reasons, reasonable extension of time will be granted on application by the contractor, but no claim for monetary compensation therefore shall be entertained under any circumstances.
42. Every tender is accepted, before quoting his rates to inspect the site of proposed work. He should inspect the quarries and satisfy himself about the quality, availability of materials, medical aids, labour, food stuff etc., and the rates shall be inclusive of all these items. In every case the materials must comply with the relevant specification. The sample of materials in sealed packets should be submitted along with the tender for approval of Block Development Officer, Pottangi while executing the work.
43. The Contractor shall have to furnish **No Relation Certificate** along with the tender as per proforma is **Annexure-I**.
44. Tenders shall be deemed valid and hold good till 90 days from the date of obtaining of tenders.
45. After completion of the work, the contractor shall arrange at his own cost all requisites and equipment's for testing for the work of building and roads and culverts etc., if found necessary and bear the entire cost of such test.
46. Tenderers are required to submit a list of important works executed by them in the State of Odisha in the prescribed form enclosed herewith accompanied by a certificate from the concerned authority of the work in respect of satisfactory and timely completion of the work.
47. Before executing the work, contractor must erect one transparency board stating a brief note on the work with specification at his own cost. No running bill will be paid unless transparency board is setup at the work site. Also, after the work is completed, necessary correction is to be made if required over the transparency board by the executants as directed by Engineer-in-Charges.
48. Tenderers should note that any extra cost for finishing & plastering of any R.C.C. Work like column, beam, chajja, roof slab etc., if any, shall not be paid.
49. The tenderer may quote reasonable rate carefully so that amount quoted should not be unworkably low or too high.
50. The Panchayat Samiti reserves the right to reject any or all tenders received without assigning any reason whatsoever. The Panchayat Samiti also reserves the right accept any tender without assigning any reasons to other tenders.
51. The Engineer-in-Charges shall have the power to make any alternations in or addition to the original specification, drawing, designs and instructions that may appear by his to be necessary or advisable during the progress of the work. The Contractor shall be bound to carry out the work in accordance with any instruction, which may be issued to the contractor after being signed by the Engineer-in-Charges and such alternation shall not invalidate the contract and any additional work which the contractor may be directed to do the manner, above, specification as part of the work shall be carried out by the contract on the same conditions in all respects on which he agreed to do the main work. The time for the completion of the work shall be extended in the proportion that the additional work bears to the original work shall be extended in the proportion that the additional work bears to the original contract work and the certificate of the Engineer-in-Charges shall be conclusive as to such proportion, and if the additional work included any class of work shall be carried out at the rate entered in the sanctioned schedule of rates of the locality during the period when the work is being carried on and if such mentioned class of work is not entered in the schedule or rate of the District then the contractor shall within seven days of the date of his receipt of the order to carry out the work, inform the Engineer-in-Charges of the rate of the which it is his intention to charge for such class of work and if the Engineer-in-Charges of the rate which it is his intention to charge for such class of work and if the Engineer-in-Charges does not agree to this rate, he shall notice in writing be at liberty to cancel his order to carry out such class of work and arrange to carry it out in such manner as may be consider advisable provided always that the contractor shall commence work of any expenditure in regard thereof before the rates shall have been determined as lastly here in before mentioned when and in such case he shall only be entitled to be paid in respect of the determination of the rate as aforesaid according to such rate of determination of the rate as shall be fixed by the Engineer-in-Charges. In the event of dispute, decision of the chairman of the Panchayat Samiti will be final.

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

52. Tenderers are required to go through each clause of the percentage rate contract from of the Panchayat Samiti carefully in addition to the clause herein before tendering.
53. Rates quoted should be fairly reasonable. Rates containing abnormal superfluous and unworkable are liable for rejection.
54. Item of work not covered in the tender schedule will be paid at the Current Schedule of Rates of the Public Works Departments, and those not covered by S.R. will be paid on actual analysis approved by the Engineer-in-Charges.
55. Standard Public Works Department specification of the Govt. of Odisha will be followed in executing the work.
56. The time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall be reckoned from the date on which the written order commence work is issued to the contractor. The work shall throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the contract on the part of the contractor) and the contractor shall pay the compensation and amount that equal to 1/3rd percent of the amount of the estimated cost if the whole works shown by the tender for every day that the whole work remain un commenced or during the execution of the work the contractor shall be bound, in all case in which the time allowed for any work exceed on month, to complete one fourth to whole of the work before three fourths of such ties has lapsed in the event of the contractor failing to comply with the condition, he shall be liable to pay as compensation an amount equal to one third percent of the said estimate cost of the whole work for every day that the due quantity or work remains in complete provided always that the entire amount for compensation to be paid under provisions of this clause shall not exceed 10 percent on the estimated cost of work as shown in the tender.
57. B.D.O., Panchayat Samiti, Pottangi who is the Chairman of the Tender committee or Panchayat Samiti, Pottangi reserves the right to blacklist any contractor for improper execution of work or importunate progress of work.
58. Measurement will be taken and payment will be made for M.S. Rods and reinforcement grills as per the actual length and weight of M.S. Rods utilized in works. The weight of binding wires and cut pieces will not be considered for payment.
59. 3.5% ("B", "C" & "D" Class) will be deducted from each payment of bill on gross value towards security deposit money. This security money is excluding EMD & ISD payments towards EMD & ISD will be paid to the contractor without any interest on application after one year of completion of work provided the final bill is paid and the defects if any pointed out within one year of completion for work have been rectified by the Contractor. S.D. shall be refunded after audit only. In case building works, if there is any leakage in slab or chajja the S.D. will be utilized by Panchayat Samiti for tar felting.
60. 2.26% of each bill shall be deducted on gross value towards income tax deposit, where the contract exceeds Rs.10,000/-.
61. No monetary compensation will be entertained on account of natural calamities like cyclone, earth quake, flood and heavy rain fall etc., but suitable extension of time may be granted by on consideration of the application of the contractor and that too only on valid reasons. No escalation claim will be entertained during the time period and extension period.
62. The earth work for roads will be done & assessed as per actual pit excavated or by section measurement on actual level section taken by the Engineer-in-Charges of the work.
63. Rubble Stone, Boulders, Rough Stone, Soling Stones and over size Metals measured by volume of closely packed stacks. 1/6 of the volume for voids will normally by deducted from closely packed stacks. For loosely packed stacks percentage of voids will be determined on actual observation and deducted as assessed at site by Engineer-in-Charges.
64. 12.50% will be deducted from metal and moorum towards void. The box heaps of 1.50 x 1.50 x 0.50 m to be measured as one cum. similar measurement to be adopted for gravel stacks and voids deducted. The rates should be excluding voids.

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

55. Sand will be measured in box heaps of 1.50 x 1.50 x 0.44 m being taken as one cubic meter or as directed by the Engineer-in-Charges of the work.
56. Road Roller should be arranged by the Contractor at his own cost for consolidation work. Hire and running Charges of the roller shall be borne by the Contractor.
57. Maintaining traffic, cutting trenches from road side lines and watching, providing signals and providing diversion road etc and maintenance for them till completion of work should be done by the contractor at his own cost.
58. It is contractor responsibility to correctly demarcate the road alignment, centre line and edge line of the road and formation width metalling width and soling width and fencing line etc., for execution of work as directed by the Assistant Engineer/Junior Engineer. All expenditure in connections with T&P instruments materials etc., required for this purpose shall be borne by the Contractor.
59. The quantities of item of work may vary at the time of actual execution of the work. The Contractors should do the work at his tendered rate whatsoever the quantity may be without any extra claim.
70. Compacted thickness as of soling stone and metal including consolidation of fill materials for which no claim for extra payment shall be entertained.
71. Only clean hand broken stone chips or Crusher broken chips shall be allowed for R.C.C. Work as the case may be as stated in Tender Schedule or as directed by Engineer-in-Charges.
72. Five percent will be deducted for voids of chips of size 6mm and above.
73. The Contractor shall sign on the plan and document for service connection (Such as P.H.D. and Electric) as and where required by the Department or house owner otherwise the security money of the contractor will not be released.
74. If the Contractor quotes abnormal low rates for any item and the Departmental decides to accept him tender, the Deptt. would have discretion of withholding the differential cost, between such highly low rates items and schedule or rates from their first, payment due against other items till such low-rate items are executed.
75. No excess over and above the estimated rates shall be allowed. In case, the lowest tenderer fails to negotiate his rates to estimated rates, the documents shall be forwarded to the Govt. for approval. However, tender committee is the final authority on the matter for forward the tender documents in such cases of excess.
76. No empty Cement Bags will be taken back by the B.D.O., Pottangi and the cost of the same will be recovered from the bill.
77. Engineer Contractor will be availed 3 Nos. of works without E.M.D. in a financial year and exemption of the E.M.D. should be entered in the Original Contractor Registration Certificate as per Works Department letter No. FA-R-11/201-10003 dated 24.05.2001.
78. To rescind the contract (of which recession notice in writing to the contractor under the hand of the accepting authority shall be inclusive evidence) 20% value of the left-over work will be realized from the contractor as penalty.
79. Engineering contractors or ST & SC contractors those availed the Govt. facilities for execution of contract should submit an affidavit with the Tender Documents that they should not sublet the work to any other contractor or person, otherwise their tender will be liable for rejection. If the successful contractor allowed to subletting the work to other contractor or person, they would be penalized and blacklisted.
80. On road works/ irrigation works the contractor make the diversion of road at his own cost if needed.

80 (Eighty items) only.

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput


(ANNEXURE-I)

NO RELATIONSHIP CERTIFICATE

1. Certified that I am/we are not related to any officers of Panchayat Samiti, Pottangi in the rank of Junior Engineer and above, any officer of the rank of Asst. Secretary and above in the Panchayati Raj Department and I am/ We are aware that the facts subsequently proved to be false my/our contract will be rescinded with forfeiture of E.M.D. and total security deposit and I/ We shall be liable to make good the loss or damage resulting from such cancellation.
2. I/We also note that non-submission of this certificate with the tender will render my/our tender liable for rejection.

Signature of the Contractor

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput
Page 10 of 15

BEFORE THE NOTARY PUBLIC DIST: KORAPUT, ODISHA AFFIDAVIT FOR PRICE PREFERENCE OF RESERVED CATEGORY CONTRACTOR (SC/ST)

I Sri _____ aged about _____ Years,
Son/ Daughter of _____ Residence of _____ Post- _____
P.S. _____ in the district of Koraput, Odisha do hereby solemnly on oath and stated
as below;

- a) That I am originally belongs to " _____ " by tribe/ Caste as such a member of
_____ certificate issued by the Tahasildar _____ vide Misc. Certificate
No. _____ dated _____ (Xerox copy Caste Certificate is enclosed for ready reckoned)
- b) That I am eligible to get the benefit being the **Reserved Category Contractor** towards 50% deposit
of the performance Security Deposit (Earnest Money Deposit & Initial Security Deposit) under rule-
13 of P.W.D Contractors Registration Rules, 1967 (**Clause-3**) and 10% price Preference in
relaxation of Rule-8 of the OGFR Vol-I and Para No. 3,5,14 of OPWD code (**Clause-2**) in pursuance
to the Resolution No. 27748_III(C) _ 16/1977/W, Dated the 11th October, 1977 of Works
Department, Govt., of Odisha.

Signature of Contractor


14/9/23
Block Development Officer, Pottangi,
Pottangi, Dist. Koraput
Page 11 of 15

(Annexure-II)

WORK EXPERIENCE

LIST OF SIMILAR NATURE OF PROJECTS EXECUTED

(30% of Tender Amount)

Name of Employer	Name of Location & Name of Work	Contract Price in Indian Rupees/ Agreement No.	Major items of Works	Stipulated date of Commencement/ Completion of the works as per Agreement	Actual date of Completion of the work	Value of work actually executed during last 5 financial years		Reasons for delay in starting/ completion if any.
						Financial Year	Value	
1	2	3	4	5	6	7	8	9

Note: - The above information is to be certified by the Engineer in Charge/ Employer not below the rank of Executive Engineer.

Signature of Contractor



14/9/23
Block Development Officer
Pottangi, Dist. Koraput
Page 12 of 15

Existing Commitments and Ongoing Works

Description of Works	Place & State	Contract No.	Name & Address of Employer	Value of Contract (Rs. In Lakh)	Stipulated period of Completion	Value of works remaining to be completed (Rs. In Lakh)	Anticipated date of completion
1	2	3	4	5	6	7	8

*Attach Certificate(s) from the Engineer-in-charge

Signature of Contractor



Block Development Officer, Pattangi
Block Development Officer
Pattangi, Dist. Koraput

(To be filled by the Contractor)

1. Name of the Contractor :
2. Permanent Address :
3. Present Address :
4. Telephone No. :
5. Designation of the License Issuing Authority :
6. (a) Date of Issue of License.
(Enclose Attested Xerox Copy of License) :
7. Valid of License : Up to
8. Pan Card No. (Enclose Attested Xerox Copy
of Pan Card) :
9. Valid VAT clearance certificate
(Enclose Attested Xerox Copy of STCC) :
10. E.M.D. Pledged : Rs /- in shape of
..... in favour of
B.D.O., Pottangi.

Signature of the Contractor

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput


NOTES: -

1. The Contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate is mentioned the tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the Contractor shall be accurately filled in figures and words, so there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the Contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The Contractor will write percentage excess or less up to two decimal points only. If he writes the percentage excess or less up to three or more decimal points, the first two decimal points shall only be considered without rounding off.

For official use only:

1. Cost of Tender Papers	:	Furnished/ Not Furnished.
2. Earnest Money Deposit	:	Furnished/ Not Furnished.
3. Copy of Valid Contractor's Registration Certificate	:	Furnished/ Not Furnished.
4. Copy of Valid GST Registration Certificate & GSTIN	:	Furnished/ Not Furnished.
5. GST Clearance Certificate	:	Furnished/ Not Furnished.
6. I.T.C.C./Pan Card	:	Furnished/ Not Furnished.
7. No Relation Certificate	:	Furnished/ Not Furnished.
8. Valid VAT Clearance Certificate	:	Furnished/ Not Furnished.
9. Original affidavit regarding authenticity of documents	:	Furnished/ Not Furnished.
10. Similar Nature of Work	:	Furnished/ Not Furnished.
11. Existing Commitments & Ongoing Works	:	Furnished/ Not Furnished.
12. Caste Certificate, if any	:	Furnished/ Not Furnished.

Signature of Contractor


Block Development Officer, Pottangi
Block Development Officer
Pottangi, Dist. Koraput

TENDER SCHEDULE

NAME OF THE WORK :---	CONSTRUCTION OF 6 NO'S OF ADDITIONAL CLASS ROOM IN GANGESWARI, DEGREE MAHAVIDYALAYA, POTTANGI
SCHEME :--- / 2022-23	BLOCK:- POTTANGI
ESTIMATE COST :-- ₹ 7500000/-	G.P:- POTTANGI
AMOUNT PUT TO TENDER :-- ₹ 4707333/-	
COST OF TENDER PAPER :- ₹ 6000/-	E.M.D REQUIRED:-- ₹ 47100/-

PERIOD OF COMPLETION:--6 (SIX) MONTHS	CLASS OF CONTRACTOR :--"B" & "A"
--	----------------------------------

Sl.No	Item of Work	Qty.	Unit	Estimated Cost (In Rs)	
				Rate	Amount
1	2	3	4	5	6
1	Earthwork excavation in hard of soil including stoney earth in foundation with all lifts, delifts and leads including dressing and levelling the bed and depositing excavated earth at place away from work site including dewatering, shuttering, cost of labour, royalty and T&P sundries required for the work etc. complete as per direction of Engineer-in-Charge.	132.03	100 Cum	24212.00	31967.00
2	Supplying and filling in foundation trenches and plinth, ditches with sand well watered and rammed in layers not exceeding 23 cm. in depth with all lead and lift including cost, conveyance, loading, unloading, royalties and taxes of all materials, cost of all labour, sundries, T&P required for the work etc. complete in all respect as per direction by the Engineer in charge.	99.50	100 Cum	117739.60	117151.00
3	Cement concrete of proportion (1:3:6) in foundation and floors using 4cm size clean hard black C.B granite stone metal of approved quality and from approved quarry including hoisting, lowering and laying concrete in layers not exceeding 15 cm. (6") thick to the required level ramming, watering, curing etc. complete including cost, conveyance, royalties and taxes of all materials with all labour and T&P required for the work etc. complete in all respect and as per the direction of the Engineer-in-charge.	52.04	One Cum	5789.60	301291.00
4	Random rubble stone masonry in c.m(1:6) in foundation and plinth by using hard black broken granite stone including bond stones from approved quarry including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering, curing including cost, conveyance, royalties and taxes of all materials with all labour and T & P required for the work complete in all respect as per direction of Engineer-in-Charge.	31.02	One Cum	4442.60	137809.00
5	C.B brick masonry in cement mortar (1:6) in super structure using C.B. Bricks 23cm x 11cm x 8cm size having crushing strength not less than 35Kg/sqcm with dimension tolerance + 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance, royalties and taxes of all materials with all labour and T & P required for the work complete in all respect as per direction of Engineer-in-Charge.				
(A)	GROUND FLOOR	34.20	One Cum	4927.80	168531.00
(B)	1st FLOOR	39.39	One Cum	5215.50	205439.00

1	2	3	4	5	6
6	Cement concrete of prop (1:2:4) with 12 mm size hard granite C.B chips of approved quality from approved quarry free from weathered skins and foreign materials including hoisting, lowering and laying concrete in layers not exceeding 0.15 mtr. in depth, watering and curing for 21 days etc complete including cost of all materials, conveyance, taxes, cess, royalty of materials with labour, concrete mixer, vibrator, t&p, sundries, for the work etc. complete as per the direction of Engineer-in-charge.				
(A)	GROUND FLOOR	3.78	One Cum	7169.40	27100.00
7	R.C.C. work of M20 in following works using 12 mm. to 20 mm. (½" to ¾") size (20 mm. not to exceed 25%) hard black crusher broken granite stone chips of approved quality from approved quarry including hoisting, lowering, laying and compacting concrete, watering curing, centering, shuttering and finishing the exposed surfaces smooth with cost, conveyance, royalties, taxes of all materials with all labour and T & P required for the work etc. complete in all respect but excluding the cost and conveyance of M.S. rods or Tor steel and binding wire of 18 to 20 gauge and labour charges for straightening, cutting, bending, binding and tying the grills and placing in proper position and as per the direction of the Engineer-in-charge.				
	GROUND FLOOR				
(A)	Coloumn Base	17.55	One Cum	6530.00	114602.00
(B)	Coloumn	10.17	One Cum	14269.70	145123.00
(C)	Plinth Beam	8.51	One Cum	7348.70	62537.00
(D)	Lintel	3.66	One Cum	13553.60	49606.00
(E)	Chajja	1.21	One Cum	17550.60	21236.00
(F)	Roof Beam and Beams	11.00	One Cum	14269.70	156967.00
(G)	Stair Slab	1.25	One Cum	14223.60	17780.00
(H)	Slab	27.37	One Cum	12898.60	353035.00
	1st FLOOR				
(A)	Coloumn	5.94	One Cum	15979.40	94918.00
(B)	Lintel	3.66	One Cum	15120.10	55340.00
(C)	Chajja	1.21	One Cum	19916.50	24099.00
(D)	Roof Beam and Beams	8.94	One Cum	15979.40	142856.00
(E)	Slab	27.17	One Cum	14334.10	389457.00
8	Providing, Cutting, straightening coiled or bent up M.S. Rod or tor steel of primary steel producers such as SAIL / Tiscon / RINL (grade Fe-500D) etc. including bending, binding, welding and jointing if necessary and tying the grills and placing in position as required for R.C.C. Work and for providing fan hooks as required, hoisting, lowering, laying including cost, conveyances, taxes of M.S. Rod or tor steel and binding wires of 18 to 20 gauge and labour required for the work for bending, binding and tying the grills in all floors (payment will be made on standard weight of B.I.S. for M.S. Rods or tor steel only) etc. complete as per specification & direction of Engineer-in-charge.				
(A)	GROUND FLOOR	92.37	One Qtl.	8585.60	793052.00
(B)	1st FLOOR	51.19	One Qtl.	8611.30	440812.00

1	2	3	4	5	6
9	Providing 2.5cm thick Grading Concrete over roof slab with cement concrete (1:2:2) using 6mm size black hard granite crusher broken chips and screened & washed sharp sand for mortar and finished smooth to the rough surface of slab including watering and curing with cost, conveyance, royalties and taxes of all materials with cost of all labour, and T&P required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	1st FLOOR	217.35	One Sqm.	365.70	79485.00
10	Providing 12 mm thick cement plaster with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	208.03	One Sqm.	164.20	34159.00
(B)	1st FLOOR	208.03	One Sqm.	170.10	35386.00
11	Providing 16 mm thick cement plaster with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	270.64	One Sqm.	231.50	62653.00
(B)	1st FLOOR	286.91	One Sqm.	236.80	67940.00
12	Providing 20 mm thick cement plaster over stone work with cement mortar of mix (1:6) with screened and washed sharp sand for mortar and finished smooth to the rough surface of walls in all heights after racking out joints including watering and curing, rounding of corners, providing grooves where ever necessary with cost, conveyance, royalties and taxes of all materials with cost of all labour, T&P, and scaffolding required for the work etc. complete in all respect as directed by the Engineer in charge.				
(A)	GROUND FLOOR	19.18	One Sqm.	244.90	4697.00
13	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, cost of all labour, T&P etc. required for the complete in all respect as per direction of the Engineer-in-charge.				
(A)	GROUND FLOOR	104.78	One Kg.	285.10	29873.00
14	Labour for fixing of door, window and grills including all concrete works, hold fasts curing etc. complete as per the direction of EIC.				
(A)	GROUND FLOOR	14.99	One Sqm.	93.32	1399.00
(B)	1st FLOOR	14.99	One Sqm.	93.32	1399.00
15	Supplying, fitting, fixing of Window (Sliding type) made up aluminium section 9778 as windows frame, section no 4095,4096 and 9777,3994, as shutter fram with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P excluding cost of glass etc. complete as per direction of Engineer-in-charge.				
(A)	GROUND FLOOR	71.24	One Kg.	700.60	49911.00
(B)	1st FLOOR	71.24	One Kg.	700.60	49911.00

1	2	3	4	5	6
16	Supplying, fitting and fixing of 5 mm thick black glass(I.S.I) in wooden or steel window frames including cutting grooves etc. complete in all floors and as per direction of Engineer-in-charge.				
(A)	GROUND FLOOR & 1st FLOOR	29.00	One Sqm.	705.01	20445.00
17	2.5 cm thick AS flooring with CC (1:2:4) including punning with 12 mm size c.b.g. chips from approved quarry including t&p with cost, conveyance, royalty and taxes of all materials to work site with all lifts and dilifts including watering and curing with all labour required for the work etc. complete as per the direction of EIC.				
(A)	GROUND FLOOR	206.18	One Sqm.	349.10	71977.00
(B)	1st FLOOR	188.53	One Kg.	360.10	67890.00
18	Finishing plastered surfaces of walls with cement base wall putty of approved make and finishing the surface smooth and even by sand papering to receive paint in walls, at all heights with staging wherever necessary with cost, conveyance, taxes of all materials, cost of all labour, all T&P etc. required for the work complete in all respect as per the direction of the Engineer-in-charge.				
(A)	GROUND FLOOR	454.67	One Sqm.	69.90	31781.00
(B)	1st FLOOR	475.44	One Sqm.	72.30	34374.00
19	Painting two coats with weather coat(I.S.I) paint (1st quality) exterior grade of approved make & shade manufactured by reputed manufacture like Nerolac / Asian / Berger / Dulex or equivalent to make an even finished surface over a coat of water bond cement primer in all heights with all scaffolding and staging charges including cost, conveyance, taxes of all materials, cost of all labour, T&P etc. complete as per the direction of the Engineer-in-charge.				
(A)	GROUND FLOOR	227.03	One Sqm.	147.30	33442.00
(B)	1st FLOOR	208.03	One Sqm.	152.70	31766.00
20	Painting two coats with plastic emulsion paint over a coat of water bond cement primer to make an even finished surface in all floors and heights to wall surface of approved make and shade including sand papering, applying putty wherever necessary & cost of scaffolding, staging charges with cost, conveyance, taxes of all materials, cost of all labour, T&P etc. complete as per the direction of the Engineer-in-charge.				
(A)	GROUND FLOOR	454.67	One Sqm.	154.20	70110.00
(B)	1st FLOOR	475.44	One Sqm.	157.40	74834.00
21	Painting two coats with synthetic enamel paint of approved shade over a coat of primer to new iron doors & windows and grills including sand papering, polishing the surface smooth to give an even shade with cost of paints, conveyance, taxes of all materials and labour with T&P required for the work etc. complete as per the direction of EIC.				
(A)	GROUND FLOOR	7.49	One Sqm.	210.50	1577.00
(B)	1st FLOOR	7.49	One Sqm.	215.80	1616.00
TOTAL AMOUNT PUT TO TENDER					4707333.00

NUMBER OF ITEMS :- 21 (TWENTYONE)

(Rupees forty seven lakh seven thousand three hundred thirty three)Only

REMARKS:-TENDER RATE QUOTED EXCESS THEN THE ABOVE TENDER AMOUNT WILL NOT BE ACCEPTED

PERCENTAGE RATE TO BE QUOTED BY THE TENDERER :-

% LESS

THEN THE ABOVE TENDER AMOUNT PUT TO TENDER

(QUOTE RATE BOTH IN FIGURE & WORDS CLEARLY)

BLOCK DEVELOPMENT OFFICER
Block Development Officer
Pottangi, Dist. Koraput

SIGNATURE OF THE CONTRACTOR